

## **Historic, Archive Document**

Do not assume content reflects current scientific knowledge, policies, or practices.



# FEASIBILITY STUDY OF REQUIREMENTS FOR MAIN DRAINAGE CANALS



## WILLIAMSBURG COUNTY SOUTH CAROLINA

Prepared Under Sponsorship of  
WILLIAMSBURG COUNTY  
WILLIAMSBURG COUNTY BOARD OF COMMISSIONERS  
and  
WILLIAMSBURG SOIL AND WATER CONSERVATION DISTRICT  
In Cooperation With The  
U. S. Department Of Agriculture  
Soil Conservation Service

# NATIONAL

A  
G  
R  
I  
C  
U  
L  
T  
U  
R  
A  
L



LIBRARY

HOW TO U

TA" SHEETS

To find information  
this Drainage Feas

eral Ditch Contained in  
s should be taken:

1. The approxin
2. Refer to fig  
on this map.
3. This index m  
drainage pla
4. Turn to the  
map. When t  
Number" and,  
L-2, etc.

should be known.

TS" and locate the area

e map sheet showing the

the area desired on this  
now the "Planning Area  
such as M-1, M-2, L-1,

5. Turn to this planning area number in the ENGINEERING AND DESIGN DATA  
sheets and locate the main or lateral desired on this sheet.

Each time a lateral enters the main canal, the Main is broken into a  
section at this point. Laterals also are broken into sections at points  
where other laterals enter them. This was necessary to design each  
section to carry the flow increase. Also, it was necessary to break mains  
and laterals into sections at state and county road crossings in order to  
design the proper size culverts and bridges at these points.

It must be kept in mind that the information given in the "ENGINEERING AND  
DESIGN DATA" sheets begins at the upper end of each watershed and proceeds,  
section by section, to the outlet.

EXAMPLE: To find information for Hollimans Swamp where it is crossed by  
County Road No. 35, approximately two miles north of the community of  
Greeleyville, refer to Figure 3, "Index to Map Sheets." The index  
indicated that the point where Hollimans Swamp is crossed by the highway  
can be found on Sheet 5 of the maps at the back of the report.

Sheet 5 designates Hollimans Swamp as Main Canal No. 1, (M-1) of Planning  
Area Number 11. It also shows Lateral No. L-3 (L-3), to be the last  
lateral entering M-1 upstream from the highway crossing.

A general description of Planning Area Number 11 is found on page 12 of the  
report and the detailed Engineering and Design Data Table is on page 57.

Beginning at the upstream end of M-1 in the table for Area 11 on page 57,  
and proceeding downward toward its outlet end, it is found that M-1 is  
crossed by the highway 1500 feet downstream from the point where L-3 enters  
M-1. The various criteria for engineering and design may be obtained from  
the table at this line.

1392

*Foreword*

Since the first settlement was made in the Williamsburg Township in November 1732, the existing imperfect internal and surface drainage problem has retarded the growth and development of this area in South Carolina.

The higher areas of land were used by the first settlers for homesteads and for small fields to produce food crops. Low, wet lands were left in their natural state. As settlements grew and more land was needed for farming operations, it was necessary to install some type of drainage system on individual farms. These drainage systems were usually excavated by hand, many with slave labor. As a result, these small ditches were inadequate and only partially met the drainage needs. The lack of knowledge about drainage systems and the absence of the necessary construction equipment prohibited the design and installation of complete systems. Improving the quantity and quality of agricultural crops and providing well drained areas for home sites are essential to perpetuate economic growth of Williamsburg County. Providing additional drainage is necessary as a first step toward enhancing the environment and increasing income for the people of Williamsburg County.

With the increase in land use and particularly with the advent of modern construction machinery such as the bulldozer, dragline and backhoe, it became relatively easy to excavate larger canals and outlet ditches needed for adequate drainage. With use of these machines, a number of ditches have been excavated in recent years in scattered locations over the county.

The Feasibility Study of Requirements for Main Drainage Canals in Williamsburg County is the direct result of foresight and interest of the county authorities and the Williamsburg Soil and Water Conservation District Commissioners who saw the need of such a plan to enhance the potential development of the county. Agencies at all levels of government - local, county, state and federal - as well as private enterprise and numerous individuals, cooperated in the development of the plan. The Williamsburg County delegation appropriated funds for the local share of the cost of the plans including the publication of this report. Technical assistance was furnished by the Soil Conservation Service.

The plan will provide a firm basis for action by county officials in determining needed legislation and methods of financing the necessary drainage improvements as well as establishing priorities of work. The cooperation of other agencies, groups and individuals in the use of the plan also will be encouraged.

U. S. DEPT. OF AGRICULTURE  
NATIONAL AGRICULTURAL LIBRARY

JUN 14 1973

CATALOGING - PREP.



# CONTENTS

## Text

	PAGE		PAGE
INTRODUCTION AND SCOPE -----	1	DEFINITIONS OF TERMS -----	14
FACTORS AFFECTING DRAINAGE -----	2	POTENTIAL SITES FOR LAKE DAMS -----	15
Topography -----	2	TECHNICAL REFERENCES -----	16
Rivers -----	2	AUTHORITY AND ACKNOWLEDGEMENT -----	16
Rainfall -----	2	EXPLANATION OF ENGINEERING DATA	
Soils -----	2	TABLES -----	18
Land Use Changes -----	5	ENGINEERING AND DESIGN DATA	
Existing Drainage System -----	5	Area 1 - Hemingway - Union	
Maintenance -----	5	Crossroads - Outland -----	21
DRAINAGE PRINCIPLES -----	6	Area 2 - Indiantown - Stuckey -	
Surface Drainage -----	6	New Morrisville -----	25
Sub-surface Drainage -----	6	Area 3 - Nesmith - Rhems -	
The Drainage System -----	6	Warsaw -----	29
Drainage Requirements -----	6	Area 4 - Cades - Roper Crossroads -	
DESIGN CRITERIA -----	7	Cedar Swamp -----	31
Drainage Coefficients -----	7	Area 5 - Millwood - Trio -	
Velocity -----	7	Sutton's -----	36
Channel Cross Section -----	9	Area 6 - Bloomingvale - Earle -	
Culverts and Bridges -----	9	Wee Tee -----	40
Right-of-way Requirement -		Area 7 - Kingstree - Cades -	
Spoil Bank Management -----	10	Moore's -----	44
DESCRIPTION OF AREAS -----	11	Area 8 - Kingstree -	
Area 1 - Hemingway - Union		Boggy Swamp -----	47
Crossroads - Outland -----	11	Area 9 - Salters - Lane -	
Area 2 - Indiantown - Stuckey -		Gourdin -----	50
New Morrisville -----	11	Area 10 - Hebron - Mouzon -	
Area 3 - Nesmith - Rhems -		Bennett Swamp -----	54
Warsaw -----	11	Area 11 - Greeleyville -	
Area 4 - Cades - Roper Crossroads -		Heineman -----	57
Cedar Swamp -----	11	MAPS SHOWING THE DRAINAGE PLAN	
Area 5 - Millwood - Trio -		Follows Page -----	59
Sutton's -----	11		
Area 6 - Bloomingvale - Earle -			
Wee Tee -----	12		
Area 7 - Kingstree - Cades -			
Moore's -----	12		
Area 8 - Kingstree -			
Boggy Swamp -----	12		
Area 9 - Salters - Lane -			
Gourdin -----	12		
Area 10 - Hebron - Mouzon -			
Bennett Swamp -----	12		
Area 11 - Greeleyville -			
Heineman -----	12		
FACTORS CONSIDERED IN PREPARATION			
OF PLAN -----	13		
ENGINEERING CONSIDERATIONS -----	13		
Design -----	13		
Acquisition of Rights-of-way -----	13		
Maintenance of Channels -----	14		
Obstructions -----	14		

## Figures

Figure No. 1 - Drainage	
Coefficient Curves -----	8
Figure No. 2 - Typical Main Ditch	
Cross Section Showing Basis for	
Determining Right-of-way Width -----	10
Figure No. 3 - Index to Map	
Sheets - Follows Page -----	59

## Tables

Table No. 1 - Total Inches	
of Precipitation -----	3
Table No. 2 - Precipitation	
Extremes -----	4
Table No. 3 - Rainfall in Inches	
for Selected Durations -----	4
Table No. 4 - Potential Dam	
Site Locations -----	15
Table No. 5 - Summary of Quantities	
and Costs by Areas -----	19

2001  
FEASIBILITY STUDY  
OF REQUIREMENTS FOR MAIN DRAINAGE CANALS  
WILLIAMSBURG COUNTY, SOUTH CAROLINA

### *Introduction and Scope*

The first logical step in solving the drainage problem in Williamsburg County is a feasibility study of the need and requirements for main drainage canals and ditches to remove the excess water. The purpose of the study is to point out the extent and severity of the drainage problem and to furnish a guide to determine the physical feasibility and the estimated costs of the needed improvements. To accomplish this, a preliminary design for a system of main drainage canals for the major watersheds of the county was made and is included in this report.

The data in this report is based on reconnaissance surveys, information presently available, and knowledge gained by long experience in planning and establishing drainage facilities in the county. The data is adequate for de-

termining preliminary design and cost estimates, but is not adequate for the preparation of final construction plans, designs and costs. The data and references included can be used by engineers as guides to determine types of surveys and investigations needed for final design.

The use of most of the land in Williamsburg County is highly dependent on adequate drainage. The poor natural drainage is the principal detriment to the development of the land resources of the county. It results in frequent and costly crop damage on agricultural land, damage to property and disruption of facilities, both public and private, in urban and industrial areas. In recent years, poor natural drainage of soils has virtually prevented or deterred housing development progress where septic tank drain fields were to be installed. The need to reduce flooding through improvement of drainage canals is recognized as a problem of first priority.



*Signing the agreement.*

PROJECT SPONSORS- Representing sponsoring organizations, the above signed the Agreement for the development of the Feasibility Study of Requirements for Main Drainage Canals in Williamsburg County. L to R: C. M. Brown, Acting Chairman, Williamsburg Soil & Water Conservation District; J. Hugh McCutchen, Chairman of Williamsburg County Board of Commissioners; A. T. Chalk, State Conservationist, Soil Conservation Service; J. Henry Stuckey, State Senator, Williamsburg County.



PUBLICATION AUTHORITY - The publication was authorized by those pictured above: L to R: Frank H. McGill, Representative, Williamsburg County; LaNue Floyd, State Senator, Williamsburg County; J. Victor Rowell, Representative, Williamsburg County.

## Factors Affecting Drainage

The location of Williamsburg County, just inland from the Atlantic Seaboard, along with the county's physical features result in complex drainage problems. The physical features that contribute to these problems are topography, rivers, rainfall, soils and land use changes, all of which are inter-related. The following is a brief discussion of how these physical features affect the drainage, along with a description of the existing drainage system and its maintenance.

### Topography

Topography is a severely limiting factor affecting drainage, since the county is located on a marine terrace of the lower coastal plain. The land is generally level with slight undulations in some sections of the county, however, the removal of excess water is restricted in most sections due to inadequate outlets. The natural drains, other than the rivers, are broad, have flat grades and are heavily vegetated. In their present state, little or no channel exists, causing extreme flooding in depressed areas. An exception to this is the old Kingstree Drainage District canal system excavated about forty years ago. Some of these old ditches still carry a large amount of water but are in need of varying amounts of maintenance to restore them to full capacity.



*A costly crop loss — "flopped" tobacco — was caused by lack of proper drainage in an agricultural area.*

### Rivers

There are several large rivers and streams in the county that have a significant effect on the drainage pattern. The Santee River on the South, the Black River through the midsection, Black Mingo Creek in the northeastern section, and the Great Pee Dee River all play an indirect part in the county's drainage. The main rivers are well defined; their water levels are generally at lower elevations and provide an outlet for higher ground drainage. However, these rivers and creeks are constantly a threat to adjacent low lying areas and after heavy

rainfall periods the flood water from the rivers flood low lying areas and block outlets of tributaries. A sizeable area of the county is affected in this manner. This report does not include any study of the main streams; it does include the feasibility of improvements in the tributaries to relieve adjacent lands of flooding as quickly as possible after heavy rains when river floods recede.



*Damage to the parking area and vegetation in a rural church yard was caused by flooding from an inadequate drainage canal nearby.*

### Rainfall

U. S. Weather Bureau records, Table No. 1, show monthly and annual totals of rainfall for Kingstree and vicinity. The average annual rainfall of 48.45 inches would not cause a serious drainage problem if it were evenly distributed. The most serious drainage problems occur in low flat areas which are flooded by high intensity, short duration rain storms. During periods of excessive rainfall many unimproved and paved roads are impassable because of floods.

The design of drainage systems and supporting structures is related to the amount of runoff that can be expected from storms of differing intensities and durations. (See Table Nos. 2 & 3.)

### Soils

Soils have characteristics which decidedly influence the need for, and the degree of, drainage. Some of the more important characteristics are depth, infiltration, permeability, texture, structure, water-holding capacity, water-table depth and slope. A knowledge of these characteristics and of the engineering properties of soils is essential in planning, designing and installing an adequate drainage system. Fine (clayey) textured soils have little or no sub-surface water movement and can be drained only through removal of surface water by means of shallow surface ditches. Sandy soils, having high or fluctuating water tables, respond readily to sub-surface drainage but present problems in the design of open ditches.



TABLE NO. 1  
TOTAL INCHES OF PRECIPITATION  
KINGSTREE, SOUTH CAROLINA

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Ann'l
1935	1.92	1.76	1.94	2.85	1.87	2.13	7.39	9.07	5.30	0.22	2.84	2.25	39.54
1936	3.83	4.01	5.91	6.22	0.35	6.12	6.79	2.99	2.00	5.56	0.94	4.15	48.87
1937	3.72	4.57	1.99	5.65	1.86	3.11	5.99	5.60	5.90	2.51	3.56	2.61	47.07
1938	1.20	0.84	3.48	5.91	3.43	5.90	6.51	2.69	5.88	0.99	1.62	1.71	40.16
1939	2.30	6.31	2.86	2.50	2.42	4.92	5.26	8.24	1.42	1.37	1.12	2.05	40.77
1940	2.65	4.97	3.30	2.50	2.80	2.55	3.12	8.82	2.29	0.05	1.61	2.46	37.12
1941	1.86	1.96	6.53	6.66	0.38	11.72	5.78	4.79	1.99	1.58	0.80	10.01	54.06
1942	1.62	3.61	6.92	0.60	2.71	5.73	3.96	6.63	1.75	0.66	1.24	3.96	39.39
1943	4.20	1.59	5.99	3.19	2.61	4.05	6.87	3.48	2.00	0.00	2.97	3.31	40.26
1944	4.21	5.09	7.94	3.02	1.10	1.25	4.91	3.85	3.91	5.19	1.30	1.16	42.93
1945	1.78	3.42	2.07	2.51	3.96	5.19	7.18	7.36	18.01	2.31	1.20	7.51	62.50
1946	3.65	2.08	2.85	3.29	2.22	2.74	5.94	7.65	3.84	6.35	2.05	0.52	44.29
1947	3.20	0.16	5.22	5.11	4.04	4.99	10.24	11.96	3.95	2.76	5.23	5.23	62.09
1948	2.85	4.38	6.13	3.12	6.74	2.05	6.99	3.36	5.76	2.90	10.20	4.26	58.74
1949	0.68	5.29	1.90	2.85	1.52	9.11	3.65	8.83	2.81	1.41	2.90	1.41	42.36
1950	1.25	0.83	4.28	0.72	3.73	3.26	6.42	4.86	9.72	3.67	1.15	4.05	43.94
1951	0.73	0.93	3.99	3.61	0.71	4.57	6.82	3.74	2.76	0.22	2.86	3.26	34.20
1952	1.42	5.46	4.88	1.70	4.22	1.18	3.56	8.46	3.09	0.80	1.82	2.45	39.04
1953	2.45	5.81	5.85	0.80	3.44	3.83	2.47	9.03	4.87	0.16	3.16	6.71	48.58
1954	1.94	0.57	2.54	2.43	4.00	2.19	5.13	2.90	4.19	5.93	0.70	1.90	34.42
1955	4.58	1.71	2.81	5.18	4.64	5.21	10.39	7.05	10.51	2.29	2.32	0.92	57.61
1956	2.11	6.01	3.41	2.69	6.29	0.97	3.55	8.47	9.12	2.78	0.45	1.55	47.40
1957	1.89	2.69	4.68	1.72	6.87	3.59	6.79	4.92	4.44	0.56	5.08	3.22	46.45
1958	5.70	3.93	5.22	8.08	3.51	6.00	4.45	10.53	4.89	2.31	1.25	3.40	59.27
1959	2.93	6.25	6.01	2.55	1.34	3.65	7.38	9.66	9.09	7.81	1.35	3.83	61.85
1960	4.65	5.41	6.50	2.14	1.94	7.09	6.83	5.98	6.91	1.41	1.32	1.46	51.64
1961	1.76	5.40	2.86	9.30	3.54	4.88	6.25	7.29	3.36	0.80	2.98	1.84	50.26
1962	4.93	4.57	5.87	2.46	0.87	5.11	3.80	10.13	5.26	1.02	4.62	2.93	51.48
1963	4.66	3.46	1.09	1.25	2.50	5.53	6.09	4.78	5.77	0.41	4.77	1.74	42.05
1964	7.16	7.32	3.41	3.42	3.35	5.59	10.26	11.89	3.30	11.65	0.78	4.16	72.29
1965	1.26	6.40	9.11	3.12	5.94	9.06	6.03	6.28	1.21	1.92	1.14	1.10	52.57
1966	5.86	2.99	4.57	2.07	11.39	6.55	5.49	5.51	2.51	1.98	0.87	3.32	53.11
1967	5.55	3.23	2.40	2.45	3.88	6.08	5.99	6.47	3.19	1.05	2.25	3.49	46.03
1968	3.35	1.17	2.29	3.09	3.41	6.89	6.24	3.72	2.56	11.20	2.60	3.39	49.91
1969	2.05	3.75	4.27	3.79	3.58	11.17	1.40	12.56	2.48	2.26	3.20	3.29	53.80
1970	3.64	4.11	8.49	0.87	2.27	2.43	5.18	6.53	4.95	4.48	0.83	4.26	48.04
Average Rainfall	3.04	3.67	4.43	3.32	3.32	4.90	5.86	6.84	4.75	2.74	2.36	3.19	48.45

from: Rainfall Data, U. S. Weather Bureau  
Kingstree, S. C. Station

TABLE 2  
PRECIPITATION EXTREMES (1935-1970)

	Maximum Monthly	Year	Minimum Monthly	Year
January	7.16	1964	0.68	1949
February	7.32	1964	0.16	1947
March	9.11	1965	1.09	1963
April	9.30	1961	0.60	1942
May	11.39	1966	0.35	1936
June	11.72	1941	0.97	1956
July	10.39	1955	1.40	1969
August	12.56	1969	2.69	1938
September	18.01	1945	1.21	1965
October	11.65	1964	0.90	1943
November	10.20	1948	0.45	1956
December	10.01	1941	0.52	1946

From Rainfall Data, U. S. Weather Bureau, Kingstree, S. C. Station

TABLE 3  
RAINFALL IN INCHES FOR SELECTED DURATIONS  
WILLIAMSBURG COUNTY, SOUTH CAROLINA

	30 Min.	1 Hour	2 Hour	3 Hour	6 Hour	12 Hour	24 Hour
1 Year	1.3	1.7	2.0	2.2	2.5	2.9	3.4
2 Years	1.6	1.9	2.3	2.6	3.0	3.5	4.2
5 Years	1.9	2.4	3.0	3.3	3.9	4.6	5.4
10 Years	2.2	2.8	3.5	3.8	4.6	5.4	6.3
25 Years	2.5	3.2	4.0	4.4	5.1	6.3	7.2
50 Years	2.8	3.6	4.4	4.9	5.9	6.9	8.1
100 Years	3.1	3.9	4.9	5.4	6.5	7.9	9.2

From U. S. Weather Bureau Technical Paper No. 40 - "Rainfall Frequency  
Atlas of the United States".

These problems include: (a) sloughing of side slopes which restricts depth of cuts; (b) limitation of the velocity of flow; and (c) sedimentation.



*Residential property damage results from heavy rains and poor drainage facilities.*



*Damage to stores is caused by flooding of a main street business section in Kingstree, S. C.*

## Land Use Changes

Several changes in land use in recent years have had an adverse effect on drainage in the county. One of the most significant of these is urbanization. Areas being developed for housing, shopping centers and industry in most instances have inadequate drainage facilities. The drainage facilities now in use were established to handle the agricultural needs of the area. They are not adequate to handle runoff resulting from urbanization. Roof tops, paved roads, parking areas and compaction in combination with raised water tables resulting from septic tank drain field installation, grading of large areas and elimination of some ditches during urban development, all have created conditions approaching 100 percent runoff. As urbanization continues, the present drainage facilities will become increasingly inadequate to handle the runoff.

There is a need for regulations to insure that

adequate drainage canals and drainage structures are installed as these areas are developed.

Drainage structures in driveways paralleling streets and roads in new as well as established subdivisions are critical factors contributing to poor local drainage. Head losses alone, resulting from widespread use of under-designed culverts in residential areas, create local flooding conditions.

Culverts for road and railroad drainage generally lack capacity to handle runoff from high intensity storms and are frequently installed with invert elevations too high to drain low areas. They are serious bottlenecks to the rapid disposal of runoff and cause local flooding. Culverts are predominantly inadequate on unpaved and farm roads.

## Existing Drainage System

With the exception of some recently excavated canals, drainage systems in rural and urban areas are generally inadequate in depth and capacity and have very flat grades. Existing flat grades are the result of topography (extensive flat terrain) and also the result of discharging canals into swamps or bays which are not adequate outlets in their present state since they generally pond water for long periods of time following heavy rainfall.

An important additional factor contributing to insufficient depth and capacity is the lack of securing adequate rights-of-way for proper ditch design, spoil management, and access for maintenance. Rights-of-way, in the past, were usually limited to the width which the landowner was willing to donate; in most cases this was less than 30 feet.

Existing canals are usually located in natural water courses. However, in many instances, alignment is poor due to the fact that canals were located on existing property lines, cleared land borders, meandering branch runs or other physical features that were inconsistent with good channel flow conditions.

## Maintenance

Lack of adequate maintenance is a factor affecting the capacity of drainage canals and ditches. Most of the existing drainage canals in the county were dug by hand many years ago; some were dug or enlarged by the Works Progress Administration (WPA) in the 1930's; clumsy floating dredges were used on some of the larger ones. These methods left nearly vertical side slopes with spoil placed immediately next to the ditch. Access to practically all canals is restricted by high spoil banks which are covered by a heavy growth of trees and brush. These spoil banks, being continuous for long distances, prevent surface drainage from adjacent areas; this results in ponding behind



the banks. The extent of economic and practical maintenance by machine is very limited, at present, due to these conditions and also to the obstacle of obtaining easements, private and legal, permitting access.



*Part of soybean crop is lost as result of wet spots in a field needing sub-surface drainage.*

## ***Drainage Principles***

The purpose of this report is to present a plan for the location and needed capacity of main drainage canals. This is, however, only the first step in the establishment of a complete drainage system. Drainage systems are divided into two broad categories - surface drainage and sub-surface drainage.

### **Surface Drainage**

Surface drainage removes excess water by gravity flow from the land surface. A very important functional part of the drainage system is the provision for water movement along the surface to an outlet, without ponding. Surface water can best be moved by shallow graded channels or by forming the land surface to a uniform slope, primarily on cultivated land. Surface drainage facilities are particularly applicable to soils having slow permeability rates; surface drainage on these soils is used to prevent ponding in shallow depression areas and also to divert water from protected areas by collecting and conveying water to natural or excavated channels.

### **Sub-surface Drainage**

Sub-surface drainage removes water from beneath the surface of the soil by facilities which create a difference in hydraulic head thus resulting in the movement of water through the soil to an outlet at a lower elevation. This may be accomplished by open ditch drains or by tile drains. Open ditch drains have an added advantage in that they can also collect and remove surface water as well as sub-surface water. Tile drains require very little maintenance, and, with certain precautions, can remove surface water indirectly by providing

protected drop inlets or catch basins that simulate small storm sewer systems.

The purpose of sub-surface drainage is to lower the water table to a point where it will not interfere with plant growth or the use of the land for residential or other purposes. The minimum depth below the surface at which water tables should be maintained depends on the purpose for which the land is to be used. Water tables, fluctuating from a lower level upward to or near the surface, may not be as great a problem in agricultural areas as they would be in populated areas.



*Installation of clay or plastic drain tile is one method of sub-surface drainage in agricultural land.*

## **The Drainage System**

A drainage system is composed of three parts: the collection segment, the disposal segment and the outlet.

The collection segment is that part of the drainage system which first picks up water from the land. It may consist of shallow trapezoidal ditches having flat side slopes, V or W type ditches, bedding, or graded land surfaces in urban areas. This is the part of the drainage system which cannot be neglected if the system is to perform adequately.

The disposal segment receives water from the collection segment and conveys it, usually in an open channel, to the outlet. Generally, this report concerns itself with the disposal segment of the drainage system.

The outlet is the end point of any section of a drainage system beyond which the ditch, storm sewer, or the system no longer guides or controls the water it discharges.

## **Drainage Requirements**

The drainage system should be designed so that flooding will not occur in critical parts of the watershed for a period of time sufficient to cause damage or disrupt utilities and services. For urban areas, design should



provide for the removal of runoff from the design storm with a minimum of flooding. In agricultural areas, the degree of protection required by crops varies considerably, depending on their tolerance to the amount and duration of excess water. Truck crops are the most susceptible to damage from excess surface water, with damage occurring to some when flooded for the relatively short period of 24 hours or less. General crops such as corn and grain are less susceptible, with pasture being the least subject to water damage. Woodland areas are the least subject to damage from flooding for prolonged periods.

Poorly drained soils adversely affect the use of the land for most purposes. On agricultural land, high water tables restrict root depth; the soil temperature is lowered and air circulation is severely limited depending on the degree of soil saturation. Wet spots in the field delay farm operations and shorten the growing season.

In residential areas, poorly drained soils adversely affect the construction, maintenance and use of roads and streets in addition to the harmful effects on ornamental plants, flower gardens and lawns. These soils also limit or prohibit the development of some areas, preventing the proper functioning of septic tanks, tile field drains and thus contribute to health hazards.



*Flooded road to a house necessitated this means of transportation; crops were lost due to poor drainage.*

## Design Criteria

Since the design of drainage systems and supporting structures is based on Hydrology and Hydraulics, this report will limit itself to the application of these sciences as they apply to the solution of such problems. Data and more detailed information on the design of open channels, closed conduits, culverts and other engineering structures ultimately involved in establishing the drainage system are tabulated on the pages following this narrative section.

4-31983 7-72

## Drainage Coefficients

The drainage coefficient is the rate of removal of runoff to provide a specific degree of drainage protection to an area. Land use, soils, topography and rainfall intensities and duration determine the selection of drainage coefficients.

Three curves have been developed from which required drainage capacities of open ditches were computed, dependent on the land use. (See Figure No. 1)

The highest curve is for urban use followed in descending order by the curve for crops and the curve for woodland.

The use of these curves provides for the removal, in 24 hours time, of the following amounts of runoff:

Urban curve	- 4.39 inches
General crops curve	- 1.67 inches
Woodland curve	- 0.37 inches

The curve for urban areas reflects an approximate peak runoff for a 10-year frequency rain.



*A ditch with good cross section and spoil management serves as surface and subsurface drainage outlet for a number of landowners.*

## Velocity

The maximum safe velocity in an open channel is determined based on soil characteristics, the shape of the channel, and available means for the stabilization of the soil after construction. The optimum velocity for channels, based on soil conditions in Williamsburg County, is approximately 2 feet per second. The soils are predominantly sandy loams with sandy clay subsoils. There are some areas where sands occur, therefore the design of channels in these lighter soils must consider the need for checking erosion and bank sloughing that might occur, immediately following construction, when water tables are high.




Figure No. 1 - Drainage Coefficient Curves



Velocities were computed by use of Manning's formula:

$$V = \frac{1.486}{n} \times r^{2/3} \times s^{1/2}$$

Where: n = roughness coefficient  
r = hydraulic radius  
s = slope in feet per foot along the ditch

The proper design of a ditch cross section requires the selection of the proper value of "n". The following tabulations were used for selection of these values in the design of main canals with good alignment:

<u>Hydraulic Radius*</u>	<u>"n"</u>
Less than 2.5	.045
2.5 to 4.0	.040
4.0 to 5.0	.035
Over 5.0	.030

\* The hydraulic radius is obtained by dividing the proposed area of the channel cross section by its wetted perimeter.

Roughness coefficients were selected anticipating flow retardance features, vegetative growth and sedimentation, several years after construction. Newly dug channels with lower selected roughness coefficients will have higher velocities initially. These velocities will diminish as the flow retardance features increase the first few years.



*A small road culvert, placed high, seriously hinders removal of rainfall runoff.*

### Channel Cross Section

Depth and width of the channel are both significant considerations in design. The channel must be deep enough to intercept ground water and allow for safe disposal. The channel depth must be adequate for lateral ditches and tile drains. Other things considered to favor deeper channels with resulting narrower bottom widths are: less right-of-way is required, vegetative growth on the wetted perimeter is reduced, and conditions are less favorable for

the formation of sandbars. A channel approximately as deep as its bottom width - within practical and economical limits - will remain effective for a longer period because it has most favorable hydraulic characteristics.

A minimum bottom width of 3.0 feet was designed for main channels, which conforms to a bucket width of small dragline excavating equipment commonly available; bottom widths were selected as narrow as design and construction criteria would permit to maintain a favorable hydraulic section.

Side slopes of the ditch, as well as depth and allowable velocities, are determined primarily by topography, soil conditions, proposed maintenance methods, and a need for adequate rights-of-way. To satisfy these conditions, 1 to 1 side slopes were used for main channels in this report. Further detailed soil surveys may indicate subsoils that would allow  $\frac{1}{2}$  to 1 side slopes in many areas; this side slope has been used satisfactorily in numerous cases in the county.

In fine sands, or other unstable soils, having high water tables, sloughing of side slopes may be expected immediately after excavation. Sloughing will continue until the water table becomes established at the lower level. The problem can be controlled somewhat in wide channels by utilizing in the initial stages, a pilot channel to lower the water table, followed by final construction when the slopes have become more stabilized. If the pilot channel method is not used, a maintenance operation would be required soon after the slopes have been stabilized to restore the design cross section.



*A large road culvert at low elevation provides good drainage capacity.*

### Culverts and Bridges

Culverts generally restrict the flow of water in ditches by decreasing the flow area thereby causing a loss in hydraulic head. This was considered in designing main channels. At culverts, during design flow, the hydraulic

gradient, in most cases, was set low enough to keep the profile of the water surface well within the channel cross section in all critical areas.

The sizes of concrete pipes shown in the tables in this report were selected to pass, adequately, the expected runoff flow which the ditches were designed to carry.



*To provide unrestricted flow, a bridge over a new canal replaces the small pipe previously used to drain heavy rainfall runoff.*

The culvert sizes were determined from Hydraulic charts for the Selection of Highway Culverts (U. S. Department of Commerce, Bureau of Public Roads) and are adequate for culverts flowing with either inlet or outlet control conditions. A head loss of no more than 0.5 foot was used in the size selection from the charts.

The sizes of culverts shown are also equivalent to calculated sizes based on a modified Talbot's formula.

Talbot's formula is:

$$A = C \sqrt[4]{M^3}$$

Where: A = Necessary waterway area in sq. ft.  
M = Area drained, in acres  
C = Runoff coefficient

This formula, based on a maximum rainfall of 4 inches per hour, was modified to use a proportionate 1.67 inches per hour and a runoff coefficient C = .25.

In cases where additional culvert cross section area was needed to supplement ones already in place, the total area of culvert opening, required to pass the flow was determined by use of this modified formula.

Where culvert sizes exceed 60 inches in diameter, it was usually found more economical to use a 15-foot bridge.

## Right-of-way Requirement-Spoil Bank Management

Factors governing width of rights-of-way can best be understood by consulting Figure No. 2. The principal requirements for spoil bank management includes a right-of-way wide enough for placement and shaping of spoil into a roadway to provide a way for travel by maintenance equipment. No berm widths are needed where the spoil is to be spread and shaped to establish a roadway on top of it. A berm width of 15 feet is optimum where spoil is to be stacked and not shaped.




Figure No. 2 - Typical Main Ditch Cross-Section Showing Basis For Determining Right-Of-Way Width



## *Description of Areas*

To facilitate planning, the county was divided into 11 areas, generally along watershed divides or large drainageways regarded as adequate. This delineation allowed the study to be made of the present drainage system and its needs peculiar to each area. A brief description of each area and the features having some influence on the study of its drainage problems follows:

### **Area 1 - Hemingway - Union Crossroads - Outland**

Area 1 is located in the northeastern corner of Williamsburg County. The Great Pee Dee River runs along the northeastern border and Black Mingo Creek is on the southwestern border. These water courses provide the two major outlets for other drainageways in this area with about half of the watershed draining to each.

Most of the section between these two drainage outlets is nearly level and composed of soils described as deep and ranging from well drained to poorly drained. These soils respond to subsurface drainage very well and give good yields in tobacco, corn and soybeans grown in this area.

The town of Hemingway is located in the upper center of the area and growing residential and industrial interests around it have affected the amount of drainage runoff. This is reflected in the Engineering and Design Data for the watershed in this vicinity.

### **Area 2 - Indiantown - Stuckey - New Morrisville**

This area is a long, generally rectangular section, running north and south with Black Mingo Creek across its midsection. The creek provides the outlet for other tributaries that drain primarily a farming section in the upper half composed of level to slightly undulating land. The soils are deep and moderately well-drained to poorly drained. Subsurface drainage ditches give good results in increased yields of the tobacco, corn and soybeans.

The lower half of this area is comprised primarily of flat bays which contain wet sandy soils that are somewhat poorly drained to very poorly drained. The bays are relatively undeveloped and are mostly covered with hardwood and other swampy areas with some timber producing land. Due to its nearly level topography, drainage of this section is difficult to obtain. Wildlife is more abundant.

### **Area 3 - Nesmith - Rhems - Warsaw**

Area 3, located in the eastern central section of the county, is a small area bordered on the north by Black Mingo Creek and on the south by the Black River. These two streams provide outlets for the upper and lower farming segments while the mid-section is composed of flat bay areas which overflow periodically in small streams in several directions.

The soils in the area are nearly level, ranging from well drained to poorly drained; subsurface drainage ditches are very effective. The mid-section is covered largely by undeveloped timberland with abundant wildlife. Timber companies are developing new tree plantations in the central section of this area. Drainage patterns will influence this development.

### **Area 4 - Cades - Roper Crossroads - Cedar Swamp**

This area located in the north central section of the county is bordered on the north by Lake Swamp. It is covered by a network of swampy drainageways either running to Lake Swamp or converging into the upper reaches of Black Mingo Creek to the east.

The soils are deep and nearly level, ranging from well drained to poorly drained. They respond well to subsurface drainage and produce good general crop yields. The swamps and timberland provide much wildlife in this area and large acreages are leased for hunting rights.

### **Area 5 - Millwood - Trio - Sutton's**

Area 5 is a long narrow area extending south from the center of the county across Black River and is bordered on the south by the Santee River. The Black River, passing through the upper portion, provides the natural outlet for tributaries in more than half of this area. The Santee River is the outlet for the southernmost portion.

This area has lesser improved drainageways than the planning areas north of the Black River. It has numerous old plantations with large tracts of timberland on which hunting rights are leased.

The major portion of the soils in the area are comprised of relatively thin topsoils with clay subsoils. They can be described as nearly level and most are poorly drained. The better farm fields produce fair general crops and pasture.

#### Area 6 - Bloomingvale - Earle - Wee Tee

This area is very similar to Area 5 in its physical characteristics. Located in the southernmost corner of the county, it is crossed in the upper section by the Black River and bordered on the south by the Santee River. There are several large bay areas in the midsection. Area 6 is old plantation country and large tracts are leased for quail and deer hunting.

The soils are nearly level and poorly drained. The bay area soils are very poorly drained. Good general crops are produced on farmlands along both sides of the river in the upper portion of this area.

#### Area 7 - Kingstree - Cades - Moores

Area 7, located in the northwestern corner of the county, is comprised almost totally of the Kingstree Swamp Watershed, which outlets into the Black River at Kingstree. A large part of Kingstree Swamp was improved in the early twenties by the old Kingstree Swamp District drainage canal. To some degree, these old ditches are still effective; some need maintenance to restore their full capacity.

There are several poorly drained bays scattered over the area. The soils in the farming sections respond well to subsurface drainage and, with drainage, produce good crops of tobacco, cotton, corn and soybeans. They are good deep sandy soils and nearly level. Deer, quail and other game are plentiful in this section of the county.

Several of the largest industries in the county are located in this section. Some timberland improvement and development is being done in the midsection of this area.

#### Area 8 - Kingstree - Boggy Swamp

In this area, just south and east of Kingstree, Boggy Swamp runs from north to south and into Black River which crosses the southwest corner. These two main drainageways provide the outlets for the smaller tributaries of the area.

The western portion, in the vicinity of Black River, is covered by undeveloped swampland and swampy growth. The low-lying parts are subject to overflow and flooding and provide hunting and fishing in the section. Drainage ditches therefore would benefit only a few higher land sites.

The eastern half of Area 8 is composed of farmland on either side of Boggy Swamp. The soils are nearly level and can be greatly benefitted by drainage ditches where outlets

are improved or provided. Crops produced in this section are tobacco, corn, soybeans and some truck.

#### Area 9 - Salters - Lane - Gourdin

Area 9, located in the south central part of the county is bounded on the north by Laws Swamp and Black River and on the south by Santee River, the county line. The upper half of the area drains north into Black River and the lower end drains south into the Santee River. The middle quarter of the area, with the town of Lane in the center, is a nearly level section with few outlets.

Like Area 5, Area 9 has fewer improved drainageways than the areas north of Black River; a number of old plantations lease timberland hunting rights.

Most of the soils have relatively thin topsoil with clay subsoils. They can be described as nearly level and most are poorly drained. Some of the better farmland fields, on higher elevations, produce fair general crops and pasture. Some timber development is being done in the central section.

#### Area 10 - Hebron - Mouzon - Bennett Swamp

On the western side of the county, Area 10 is divided in the middle by Black River running west to east which provides the outlet for the upper two-thirds of the area. The lower third tributaries drain into Bennett Swamp which runs across the bottom end.

Most of the soils are nearly flat, improve with drainage and give good crop yields of tobacco, cotton, corn, soybeans and some truck. The river swamp area is subject to overflow, is undeveloped and provides hunting and fishing. Quail are abundant in the area.

#### Area 11 - Greeleyville - Heineman

Area 11 is a small block in the southwest corner of the county bordered by the Clarendon County line on the east, Santee River on the south and U. S. Highway No. 52 on the east. The town of Greeleyville is located in the center of the block with highways radiating in all directions from town.

Almost all of the drainage is toward and into tributaries of the Santee River on the south. Two bays, one southeast and one southwest of Greeleyville, occupy sizeable areas of undeveloped land as well as the Santee River Swamp which is subject to overflow.

The soils in the higher elevation areas respond to drainage ditches and yield fair gener-

al crops.

A number of old plantations have leased hunting areas.

### *Factors Considered in Preparation of Plan*

The Drainage Feasibility Study was prepared by engineers of the Soil Conservation Service with the assistance of the Williamsburg County Development Board and County Supervisor's office. On-site investigations were made of the outlets for each main canal, and the factors affecting drainage within the watershed, such as land use, river stages, flooding and the time of year in which flooding occurs, were studied.

Present land use and anticipated future land use was considered in preparing the design of needed drainage canals. Engineering information available through the Williamsburg County Work Unit office of the Soil Conservation Service was also used, particularly that pertaining to drainage investigations.

U. S. Geological Survey Topographic Maps were used to determine the general topography within each watershed and to assist in delineation of watersheds. A limited amount of instrument surveying was made to secure detailed information in some areas to determine direction of runoff and outlets.

Aerial photographs, scale 1" = 1320', flown in 1966, were used in recording field data and for the preparation of the drainage plan.

Agencies and commercial concerns, having knowledge of specific drainage problems, were consulted in making the final decisions in certain areas. Also, maps, surveys and plans available from these agencies were used.

In most instances, mains were located along natural drains with modifications in alignment to improve the flow and the collection of water. All needed laterals within the watersheds were not located since the purpose of the study is to locate and design only the main canals which will furnish the means of disposal of runoff from all parts of the watershed. All mains are terminated in rivers, creeks or natural outlets at a point where they have adequate capacity and depth.

No attempt was made to locate underground utilities such as telephone cables, gas pipelines, water mains and conduits as a part of this study. However, due consideration must be given to the location of these underground utilities during the preparation of the final plans.

In general, the drainage plan was limited to

areas considered as "high lands", that is, five feet or more above mean low water.

Watersheds draining into the county from adjoining counties were determined for the purpose of designing main canals. The mains, however, are shown beginning at the county line. Due attention was given to possible land use changes in adjacent counties that would affect runoff coming into these watersheds.

### *Engineering Considerations*

Engineering considerations for planning, design, construction, maintenance and other matters pertinent to the Main Drainage Canals Feasibility Study are listed below:

#### *Design*

The plan presented herewith is a Feasibility Study to estimate the cost and the extent of needed main drainage facilities and the physical practicability of drainage in the county. Detailed engineering surveys and designs will be required before any part of the proposed plan is constructed. All improvements should be made continuous. Layout and construction should begin at the outlet end and continue upstream.

Plans and designs contained in this report do not include a complete study of underground storm sewers near towns found in Areas 1, 7, 8, 9 and 11; there is a lack of information on original surveys and designs showing size, depth and location. Detailed studies will be needed to determine the present condition of these storm sewers and additional needs.

Culverts at railroad and road crossings were designed to satisfy the minimum requirements based on expected flow. Increases in size of these structures may be desirable to provide an added safety factor for passing runoff in excess of designed flow where future unforeseen improvements are to be made in the vicinity.

Organizations or agencies concerned with environmental protection should be consulted when the ecology of an area may be affected by the construction of main drainage canals.

#### *Acquisition of Rights-of-way*

The means for, and the acquisition of, adequate rights-of-way for the installation of main canals is absolutely essential. The right-of-way must be adequate to take care of width requirements for channel section, berm, spoil management and access. (See Figure No.2)



## Maintenance of Channels

A well organized and adequately financed maintenance program is essential to maintain design capacity in all canals.

Provision for annual maintenance or periodic reconstruction to maintain the effectiveness of the channel must be considered prior to construction. Many drainage enterprises fail to function as designed and this can be directly attributed to an inadequate maintenance program. Maintenance of designed depth of channels is one of the most important items in a maintenance program. The cost of maintenance may be reduced considerably if provision is made in channel designs for easy access and stabilization of silt-contributing areas, such as ditch side slopes, new road fills and road ditch intersections, immediately following construction.

## Obstructions

Construction of fences, walks and other structures that may retard channel flow should not be permitted. Other structures such as culverts, bridge piers, trestles, etc. should be designed to result in minimum interference with the channel flow. Dumping trash, garbage and other debris in channels should be prohibited.

## Definition of Terms

Brief descriptions of terms used in this report are listed below in alphabetical order.

c.f.s. - Abbreviation for cubic feet per second; a unit of water-flow sometimes called "second feet."

Infiltration - The entrance of water into surface horizons of soil.

Internal Drainage - The movement of water through the soil profile. The rate is affected by the texture of the surface soil and of the subsoil and by the height of the water table. A wet, deep sand may have slow internal drainage when the water table is high, and rapid internal drainage when the water table is low. A plastic, sandy clay soil may have slow internal drainage regardless of water table height.

Lateral Ditch - A major ditch in a drainage system which serves as a link between the main ditch and the collection system in a segment of the watershed.

Main Canal (Ditch or Channel) - The principal channel which conducts the drainage water from the watershed to the outlet.

Permeability Rate - The rate of movement of water through the soil.

Profile, Soil - A vertical section of the soil through all its horizons and extending into the parent material.

Reach - A length of channel selected for use in hydraulic computations.

Relief - The elevations or inequalities of a land surface, considered collectively.

Runoff, Surface - The total rainfall minus losses from interception, infiltration, evapotranspiration, and surface storage; that which moves across the ground to a stream or depression.

Runoff, Subsurface - Water that infiltrates the soil and reappears as seepage or spring flow.

Soil Drainage - (1) The rapidity and extent of the removal of water from the soil by runoff and flow through the soil to underground spaces. (2) As a condition of the soil, the frequency and duration of periods when the soil is free of saturation. For example, in well-drained soils, the water is removed readily, but not rapidly; in poorly drained soils, the root zone is waterlogged for long periods and the roots of ordinary crop plants cannot get enough oxygen; and in excessively drained soils, the water is removed so completely that most crop plants are damaged by lack of water.

Soil Structure - The arrangement of the individual grains and aggregates that make up the soil mass; may refer to the natural arrangements of the soil when in place and undisturbed or to the soil at any degree of disturbance.

Subsoil - In soils with weak profile development, the subsoil can be defined as the soil below the plowed soil (or its equivalent of surface soil) in which roots normally grow.

Surface Soil - The soil ordinarily moved in tillage or the equivalent in uncultivated soil about six to ten inches in thickness.

Terrace (Geological) - An old alluvial plain, ordinarily flat or undulating, bordering a river, lake or the sea. Stream terraces are frequently called second bottoms, as contrasted to flood plains, and are seldom subject to overflow. Marine terraces were deposited by the sea and are generally wide.

Texture, Soil - The relative proportions of sand, silt and clay particles in a mass of soil. The basic textural classes, in order of increasing proportions of fine particles are as follows: sand, loamy sand, sandy loam,



loam, silt loam, silt, sandy clay loam, clay loam, silty clay loam, sandy clay, silty clay and clay. The sand, loamy sand, and sandy loam classes may be further divided by specifying "coarse," "fine," or "very fine." A coarse-textured soil is one high in sand content; a fine-textured soil is one high in clay content.

Water-holding Capacity - The ability of a soil to hold water. The capacity (or ability) of soil to hold water against gravity.

Watershed - An area of land from which all water that falls within the area converges toward and discharges past a designated point.

### *Potential Sites For Lake Dams*

While field data was being collected for this report, several potential sites for lakes were observed across the county. These were noted and tabulated as possible sites for dams to provide the lakes. It should be understood that these sites were listed as observations only and no survey was made otherwise. It will be necessary to make a complete engineering investigation to determine their economic feasibility. The potential site locations are listed in table 4.

TABLE 4  
POTENTIAL DAM SITE LOCATIONS

Planning Area	No. of Sites	Description
Area # 1	1	On Poplar Hill Branch just north of S. C. Hwy. 512.
2	1	On Indian Town Swamp just north of S. C. Hwy. 512.
3	1	On Headless Swamp east of S. C. Hwy. 121.
4	1	On Cedar Swamp between S. C. Hwy. 261 and S. C. Hwy. 24.
5	1	On Ox Swamp north of Highway 521 east of Burrows Crossroads.
7	1	On Kingstree Swamp, north of S. C. Hwy. 44 near Fennell Field.
8	1	On Boggy Swamp, north of S. C. Hwy. 147.
10	1	On Pudding Swamp, north of S. C. Hwy. 287 near McIntosh Farms.

## *Technical References*

C. E. Ramser - FLOW OF WATER IN DRAINAGE CHANNELS - U. S. Department of Agriculture - Technical Bulletin No. 129 - U. S. Government Printing Office - Washington, D. C.

H. W. King - HANDBOOK OF HYDRAULICS - McGraw-Hill Book Company, Inc., New York, N. Y.

War Department, Corps of Engineers - HYDRAULIC TABLES - U. S. Government Printing Office, Washington, D. C.

U. S. Department of Agriculture, Soil Conservation Service - NATIONAL ENGINEERING HANDBOOK - DRAINAGE - Section 16, Chapters 1, 2, 3, 4, 5 and 6.

U. S. Department of Agriculture, Soil Conservation Service - NATIONAL ENGINEERING HANDBOOK - HYDRAULICS - Section 5.

U. S. Department of Agriculture, Soil Conservation Service - FIELD DRAINAGE GUIDE FOR SOUTH CAROLINA.

U. S. Department of Commerce, Weather Bureau - TECHNICAL PAPER NO. 40 - RAINFALL, FREQUENCY ATLAS OF THE UNITED STATES - U. S. Government Printing Office - Washington, D. C.

U. S. Department of Commerce, Bureau of Public Roads - HYDRAULIC CHARTS FOR THE SELECTION OF HIGHWAY CULVERTS.

U. S. Department of Agriculture, Soil Conservation Service - NATIONAL ENGINEERING HANDBOOK - HYDROLOGY - Section 4.

FEASIBILITY STUDY FOR MAIN DRAINAGE CANALS in Colleton County.

FEASIBILITY STUDY FOR MAIN DRAINAGE CANALS in Beaufort County.

## *Authority and Acknowledgement*

Authorization for preparation of the Feasibility Study of Requirements for Main Drainage Canals for Williamsburg County is the result of a cooperative agreement entered into on June 22, 1967 by:

Williamsburg County Legislative Delegation -

LaNue Floyd, State Senator  
J. Henry Stuckey, Member of House of Representatives  
Ernest Carter, Member of House of Representatives

Williamsburg County Board of Commissioners -

J. Hugh McCutchen, Supervisor  
T. R. Grier  
D. C. Haddock  
J. A. Mixon  
Paul Murray  
W. P. Wheeler

Williamsburg Soil and Water Conservation District

Soil Conservation Service -

A. T. Chalk, State Conservationist

## *Authority and Acknowledgement (continued)*

Publication of the report was authorized in fiscal year 1971 by:

Williamsburg County Legislative Delegation -

LaNue Floyd, State Senator  
J. Victor Rowell, Member of House of Representatives  
Frank H. McGill, Member of House of Representatives

Williamsburg County Board of Commissioners -

J. Hugh McCutchen, Supervisor  
T. R. Grier  
Roosevelt Miller  
J. A. Nixon  
W. P. Wheeler  
Moise Wilson

Soil Conservation Service -

George E. Huey, State Conservationist

Administrative supervision for Soil Conservation Service:

O. S. Kirkpatrick, Area Conservationist

Direct responsibility for preparation of plans, designs and final report:

Calvin B. Derrick, Civil Engineer, Soil Conservation Service  
Henry B. Watson, Soil Conservation Technician, Soil Conservation Service  
Mack O. Kirby, Soil Conservation Technician, Soil Conservation Service

Special technical assistance during all phases of the preparation of this report:

S. Taylor Currin, State Conservation Engineer, Soil Conservation Service  
Talbert R. Gerald, Soil Scientist, Soil Conservation Service  
James E. Driskell, District Conservationist, Soil Conservation Service

Others who furnished data or information used in the preparation of this report:

U. S. Department of the Interior  
U. S. Weather Bureau  
South Carolina Highway Department

Assistance in typing tables, charts and manuscript, gratefully acknowledged:

Miss Anne Wayne, Clerk-stenographer, Soil Conservation Service Area Office  
Florence, S. C.  
Mrs. Jewel Bailey, Clerk-typist, Soil Conservation Service Area Office,  
Florence, S. C.

Cartography and Printing:

Fort Worth Cartographic Unit, Soil Conservation Service

## *Explanation of Engineering Data Tables*

The following Engineering Data Tables contain information, by areas, for each main canal and lateral, by watersheds.

An explanation of each column in the Engineering Data sheets is as follows:

Column 1	CANAL NUMBER Numbering of main canals begin with M-1 and laterals with L-1, in each area.
Column 2	LENGTH IN FEET Stationing of all mains and laterals begins at the upper end (headwaters) and continues toward the outlet. Mains and laterals are shown in reaches or sections in the data tables for design purposes. Each reach or section reflects a change in water concentration resulting from entrance of lateral drainage.
Column 3	WATERSHED IN ACRES See definition of terms.
Column 4	DISCHARGE-CUBIC FEET PER SECOND From appropriate drainage coefficient curves dependent on land use. (See Fig. No. 1)
Column 5	TOP WIDTH IN FEET Self explanatory.
Column 6	BOTTOM WIDTH IN FEET Self explanatory.
Column 7	AVERAGE DEPTH IN FEET Self explanatory.
Column 8	EXCAVATION IN CUBIC YARDS Self explanatory.
Column 9	RIGHT-OF-WAY CLEARING IN ACRES Self explanatory.
Column 10	REQUIRED RIGHT-OF-WAY WIDTH IN FEET Minimum width requirements for channel cross section, spoil management, berm width and maintenance access road.
Column 11	CULVERTS, BRIDGES EXISTING - LENGTH & SIZE Existing in-place culverts or bridge; re-used in Col. 12 or disposition is shown by the footnote.

Column 12 CULVERTS, LOWERING-LENGTH AND SIZE  
Existing culverts shown in Col. 11 which are to be re-used by lowering to a new grade elevation.

Column 13 CULVERTS, BRIDGES AND TRESTLES NEW-LENGTH & SIZE  
Refers to additional culverts, bridges and trestles required to handle design discharge. Design is based on round concrete pipe.

R. C. Br. - Reinforced concrete bridge  
C. T. Br. - Creosoted timber bridge  
U. T. Br. - Untreated timber bridge  
C. T. Tres. - Creosoted timber trestle

Column 14 TOTAL ESTIMATED COST IN DOLLARS  
Total costs shown include only the estimated construction costs and do not include engineering costs, or the cost of acquiring required right-of-way. When preparing the final cost estimates these engineering costs and right-of-way costs should be included in the total cost of the project. Total estimated costs, as shown, are based on the following unit prices prevailing in Williamsburg County, in 1970: (A summary of total costs by areas is shown in Table 5.)

EXCAVATION  
General - \$0.25 per cu. yd.

RIGHT-OF-WAY CLEARING  
General - \$200.00 per ac.

LOWERING EXISTING CULVERTS  
Labor and equipment costs only.

NEW CULVERT AND CONDUIT COSTS  
Based on present cost of circular concrete pipe.

BRIDGES  
Precast reinforced concrete bridges were used under main highways and secondary roads.

Prevailing cost -  
\$1000 per 15' span.



TABLE NO. 5  
SUMMARY OF QUANTITIES AND COSTS BY AREAS  
FROM ENGINEERING AND DESIGN DATA

Area Number	Length of Canals (feet)	Excavation (cubic yards)	Right-of-Way Clearing (acres)	Estimated Total Cost (dollars) <sup>1/</sup>
1	284,800	534,452	247.4	211,777
2	321,000	600,955	278.7	238,798
3	195,800	374,377	172.5	150,761
4	416,100	856,906	386.5	329,423
5	281,900	555,519	253.4	208,659
6	387,200	889,809	389.9	351,580
7	308,200	148,543	69.9	57,276
8	214,800	371,628	176.1	144,446
9	324,600	631,869	289.8	239,769
10	260,500	431,391	203.5	169,305
11	251,300	469,653	215.9	183,271
<hr/>				
Sub- Totals	3,246,200	5,865,102	2,683.6	2,285,065
Plus 15% added for contingencies -				342,760
<hr/>				
County Totals	3,246,200	5,865,102	2,683.6	2,627,825

<sup>1/</sup> Based on 1971 prices.



# ENGINEERING AND DESIGN DATA

## Area 1 - Hemingway-Union Crossroads - Outland

Sheet 1 of 4

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-1	800	58	6	13	3	5	1184	0.6	38	- - -	- - -	- - -	12,037.00
M-1	9000	1302	81	27	7	5	20,000	8.9	49	- - -	- - -	- - -	
L-1	2500	172	15	13	3	5	3700	1.8	38	40' - 24"	- - -	40' - 30"	
L-1	3400	324	26	13	3	5	5032	2.5	38	40' - 30" 1/2	- - -	40' - 42"	
L-1	700	332	26	13	3	5	1036	0.5	38	- - -	- - -	- - -	
Total-1	16,400						30,952	14.3					
M-2	7400	480	35	13	3	5	10,952	5.4	38	(2) 20' - 24" 1/2	- - -	30' - 48"	24,571.00
M-2	2900	804	54	15	5	5	5365	2.5	44	- - -	- - -	- - -	
M-2	4000	1540	94	16	6	5	8160	3.7	46	(2) 30' - 24" 1/2	- - -	15' R.C. Br.	
M-2	2400	2072	120	17	7	5	5328	2.4	49	(3) 30' - 18" 1/2	- - -	- - -	
M-2	3000	3012	165	22	12	5	9450	3.9	62	- - -	- - -	- - -	
L-1	2100	128	12	13	3	5	3108	1.5	38	40' - 18" 1/2	- - -	40' - 30"	
L-1	1000	152	14	13	3	5	1480	0.7	38	40' - 18" 1/2	- - -	40' - 30"	
L-1	2700	292	23	13	3	5	3996	2.0	38	- - -	- - -	- - -	
L-2	7700	688	47	13	3	5	11,396	5.7	38	(2) 20' - 24" 1/2	- - -	15' R.C. Br.	
L-2	600	738	49	13	3	5	888	0.4	38	- - -	- - -	- - -	
Total-2	33,800						60,123	28.2					
M-3	2700	132	12	13	3	5	3996	2.0	38	30' - 24" 1/2	- - -	30' - 30"	3,067.00
M-3	2400	348	18	13	3	5	3552	1.8	38	- - -	- - -	- - -	
Total-3	5100						7548	3.8					
M-4	1500	300	24	13	3	5	2220	1.1	38	30' - 18" 1/2	- - -	30' - 42"	
M-4	3100	556	40	13	3	5	4588	2.3	38	50' - 36" 1/2	- - -	15' R.C. Br.	
M-4	5100	968	63	16	6	5	10,404	4.7	46	- - -	- - -	- - -	21,364.00
M-4	2400	1548	94	18	8	5	5784	2.5	52	45' R.C. Br.	- - -	- - -	
M-4	2000	3024	166	26	16	5	7780	3.1	73	75' Tres.	- - -	- - -	
L-1	2000	152	14	13	3	5	2960	1.5	38	6' x 6'	- - -	- - -	
L-1	3800	364	28	13	3	5	5624	2.8	38	- - -	- - -	- - -	
L-2	3600	200	17	13	3	5	5328	2.6	38	40' - 30" 1/2	- - -	40' - 36"	
L-2	2300	320	25	13	3	5	3404	1.7	38	40' - 36" 1/2	- - -	40' - 42"	
L-2	3300	456	34	13	3	5	4884	2.4	38	- - -	- - -	- - -	
Total-4	29,100						52,976	24.7					
M-5	7600	600	42	13	3	5	11,248	5.6	38	40' - 48"	- - -	- - -	3,932.00
Total-5	7600						11,248	5.6					





# ENGINEERING AND DESIGN DATA

## Area 1 - Hemingway - Union Crossroads - Outland

Sheet 2 of 4

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-6 M-6 Total-6	3400 4300 7700	260 488	21 36	13 13	3 3	5 5	5032 6364 11,396	2.5 3.2 5.7	38 38	50' - 36" - - -	50' - 36" - - -	- - - - - -	4,589.00
M-7 M-7 M-7 Total-7	2700 8400 5600 16,700	524 1604 2092	9 2/ 22 2/ 58 3/	13 13 15	3 3 5	5 5 5	3996 12,432 10,360 26,788	2.0 6.2 4.9 13.1	38 38 42	30' - 36" (2) 40' - 30" 45' R.C. Br.	- - - - - - - - -	30' - 48" 15' R.C. Br. - - -	11,097.00
M-8 M-8 Total-8	4000 3200 7200	432 788	32 54	13 13	3 3	5 5	5920 4736 10,656	2.9 2.4 5.3	38 38	(2) 40' - 36" (2) 5' x 5'	- - - - - -	40' - 42" - - -	4,604.00
M-9 M-9 M-9 Total-9	5200 2500 1100 8800	400 568 592	31 41 42	13 13 13	3 3 3	5 5 5	7696 3700 1628 13,024	3.8 1.8 0.8 6.4	38 38 38	50' - 48" 40' - 42" - - -	- - - - - - - - -	15' R.C. Br. 15' R.C. Br. - - -	6,536.00
M-10 M-10 M-10 M-10 M-10 M-10 M-10 L-1 L-2 L-2 Total-10	3800 2400 1100 1900 400 600 2600 8800 6700 3200 31,500	416 596 680 1084 1696 1756 2816 552 756 852	81 4/ 112 4/ 125 4/ 184 4/ 231 5/ 239 5/ 323 5/ 40 52 56	17 20 22 28 28 28 34 13 13 15	7 10 12 18 18 18 24 3 3 5	5 5 5 5 5 5 5 5 5 5	8,436 6,672 3,465 8,094 1,704 2,556 13,962 13,024 9,916 5,920 73,749	3.8 2.8 1.4 3.1 0.7 1.0 5.3 6.5 4.9 2.8 32.3	49 57 62 78 78 78 94 38 38 44	50' - 30" - - - - - - - - - 45' R.C. Br. - - - - - - - - - 30' R.C. Br. - - -	- -	15' R.C. Br. -	25,896.00
M-11 M-11 M-11 M-11 M-11 M-11 M-11	1800 900 2400 1300 1500 900 3800	196 260 528 552 620 1124 1440	45 4/ 57 4/ 98 4/ 102 4/ 113 4/ 190 4/ 232 4/	14 15 19 19 20 24 28	4 5 9 9 10 14 18	5 5 5 5 5 5 5	3006 1665 6216 3367 4170 3168 16,188	1.4 0.8 2.7 1.5 1.8 1.3 6.3	41 44 55 55 57 68 78	(2) 5' x 5' 30' - 24" 15' R.C. Br. (2) 6' x 6' 34' C.T. Tres. (2) 6' x 8' 20' - 30" 20' - 24"	- -	- - - 15' R.C. Br. - - - - - - - - - 30' R.C. Br. - - -	
M-11	2300	1512	238 4/	28	18	5	9798	3.8	78	- - -	- - -	- - -	

J. S. DEPARTMENT OF AGRICULTURE, SOIL CONSERVATION SERVICE  
USDA-SCS-FORT WORTH, TEX 1970

Work Sheet 3-70

4-R-29076-A



# ENGINEERING AND DESIGN DATA

Area 1 - Hemingway - Union Crossroads - Outland

Sheet 3 of 4

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
L-1	2500	164	39 4/	13	3	5	3700	1.8	38	40' - 30" L/	- - -	15' R.C. Br.	22,883.00
L-1	1400	220	48 4/	14	4	5	2338	1.1	41	- - -	- - -	- - -	
L-1	1300	400	80 4/	17	7	5	2886	1.3	49	34' C.T. Tres.	- - -	- - -	
Total-11	20,100						56,502	23.8					
M-12	1800	92	9	13	3	5	2664	1.3	38	20' - 18" L/	- - -	30' - 24"	9,322.00
M-12	2200	404	31	13	3	5	3256	1.6	38	40' - 30" L/	- - -	40' - 42"	
M-12	2500	524	38	13	3	5	3700	1.8	38	(2) 6' x 8'	- - -	- - -	
M-12	2900	708	49	13	3	5	4292	2.1	38	- - -	- - -	- - -	
M-12	1600	996	110 5/	18	8	5	3856	1.7	52	15' R.C. Br.	- - -	- - -	20,218.00
L-1	300	16	6 4/	13	3	5	444	0.2	38	(2) 8' x 8'	- - -	- - -	
L-1	3700	152	36 4/	13	3	5	5476	2.7	38	- - -	- - -	- - -	
Total-12	15,000						23,688	11.4					
M-13	9100	750	51	14	4	5	15,197	7.3	41	- - -	- - -	- - -	5,838.00
M-13	2500	1000	65	16	6	5	5100	2.3	46	- - -	- - -	- - -	
M-13	3000	1432	88	18	8	5	7230	3.2	52	(2) 8' x 8'	- - -	- - -	
M-13	2900	1564	95	18	8	5	6989	3.1	52	- - -	- - -	- - -	
M-13	500	2136	123	22	12	5	1575	0.6	62	(2) 40' - 30" L/	- - -	30' R.C. Br.	3,980.00
L-1	2800	132	12	13	3	5	4144	2.1	38	40' - 18" L/	- - -	40' - 30"	
L-1	5000	536	39	13	3	5	7400	3.7	38	40' - 24" L/	- - -	30' - 48"	
L-1	1000	556	40	13	3	5	1480	0.7	38	(2) 20' - 30" L/	- - -	- - -	
Total-13	26,800						49,115	23.0					12,400.00
M-14	2000	108	10	13	3	5	2960	1.5	38	50' - 36"	50' - 36"	- - -	
M-14	5900	596	42	13	3	5	8732	4.3	38	30' R.C. Br.	- - -	- - -	
M-14	2000	680	47	14	4	5	3340	1.6	41	(2) 5' x 5'	- - -	- - -	
Total-14	9900						15,032	7.4					3,980.00
M-15	6000	344	26 2/	13	3	5	8880	4.4	38	50' - 36" L/	- - -	40' - 42"	
Total-15	6000						8880	4.4					
M-16	5000	1808	Georgetown	County									12,400.00
M-16	2100	2056	119	22	12	5	15,750	6.4	62	(2) 50' - 48"	- - -	- - -	
M-16	1500	2992	163	26	16	5	8169	3.2	73	(3) 10' x 10'	- - -	- - -	
L-1	5500	164	15	13	3	5	2220	1.1	38	50' - 30"	50' - 30"	- - -	
Total-16	14,100	772	52	14	4	5	9185	4.4	41	- - -	- - -	- - -	12,400.00
							35,324	15.1					





# ENGINEERING AND DESIGN DATA

Area 1-Hemingway-Union Crossroads-Outland

Sheet 4 of 4

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-17 M-17 Total-17	4400 4400	40 160	12 Georgetdwn County	13 13	3 3	5 5	6512 6512	3.2 3.2	38	50' - 24" - - -	- - - - - -	- - - - - -	2,268.00
M-18 M-18 M-18 M-18 L-1 L-1 Total-18	2600 4000 2400 3100 4000 400 16,500	776 1008 1132 2044 656 688	53 66 73 118 46 48	13 14 15 18 13 13	3 4 5 8 3 3	5 5 5 5 5 5	3848 6680 4440 7471 5920 592 28,951	1.9 3.2 2.1 3.3 2.9 0.3 13.7	38 41 44 52 38 38	20' - 24" (2)40' - 24" - - - (3)20' - 24" 20' - 18" - - -	- - - - - - - - - - - - - - - - - -	15' R.C. Br. 15' R.C. Br. - - - - - - 15' R.C. Br. - - -	12,978.00
M-19 M-19 Total-19	2400 5700 8100	348 780	27 52	13 13	3 3	5 5	3552 8436 11,988	1.8 4.2 6.0	38 38	30' R.C. Br. - - -	- - - - - -	- - - - - -	4,197.00
<p>1/ Remove or abandon (Not included in designed capacity.)</p> <p>2/ Runoff curve used: Q = 10M 5/6.</p> <p>3/ Runoff curve used: Q = 45 M 5/6 for accumulated area applicable + Q curve for segment (s) using other runoff coefficients.</p> <p>4/ Runoff curve used: Q = 118 M 5/6.</p> <p>5/ Runoff curve used: Q = 118 M 5/6 for accumulated area applicable + Q curve for segment (s) using other runoff coefficients.</p> <p>NOTE: Figure in parenthesis in column 11 indicates number of culverts.</p>													





# ENGINEERING AND DESIGN DATA

## Area 2 - Indiantown-Stuckey-New Morrisville

Sheet 1 of 4

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-1	4300	824	55	13	3	5	6364	3.2	38	40' - 60" L	- -	15' R.C. Br.	
M-1	3700	994	65	14	4	5	6179	3.0	41	- - -	- -	- - -	
M-1	2500	3342	177	24	14	5	8800	3.6	68	40' C.T. Br.	- -	- - -	
M-1	4000	3842	201	26	16	5	15,560	6.2	78	- - -	- -	- - -	
L-1	2600	288	23	13	3	5	3848	1.9	38	40' - 24" L	- -	40' - 36"	
L-1	5300	768	53	13	3	5	7844	3.9	38	40' - 42" L	- -	15' R.C. Br.	
L-1	1100	804	54	13	3	5	1628	0.8	38	- - -	- -	- - -	
L-1	2000	1304	82	17	7	5	4440	2.0	49	(3) 20' - 24" L	- -	15' R.C. Br.	
L-1	4000	1924	113	20	10	5	11,120	4.7	57	- - -	- -	- - -	
L-2	2600	236	20	13	3	5	3848	1.9	38	None	- -	40' - 36"	
L-2	5500	452	34	13	3	5	8140	4.0	38	- - -	- -	- - -	
L-3	2100	136	12	13	3	5	3108	1.5	38	None	- -	40' - 30"	
L-3	5900	372	28	13	3	5	8732	4.3	38	- - -	- -	- - -	
Total-1	45,600						89,611	41.0					35,443.00
M-2	800	276	22	13	3	5	1184	0.6	38	40' - 36"	40' - 36"	- - -	
M-2	1200	312	25	13	3	5	1776	0.9	38	- - -	- -	40' - 42"	
M-2	8400	1056	68	15	5	5	15,540	7.3	44	40' - 36" L	- -	15' R.C. Br.	
Total-2	11,000	1084	69	15	5	5	19,610	9.3	44	- - -	- -	- - -	9,122.00
M-3	1600	124	11	13	3	5	2368	1.2	38	20' - 18" L	- -	30' - 30"	
M-3	3700	270	22	13	3	5	5476	2.7	38	(3) 30' - 24" L	- -	30' - 36"	
M-3	1500	318	25	13	3	5	2220	1.1	38	- - -	- -	- - -	
M-3	2500	2006	116	22	12	5	7875	3.2	62	45' R.C. Br.	- -	- - -	
L-1	2400	664	46	13	3	5	3552	1.8	38	(2) 30' - 24" L	- -	15' R.C. Br.	
L-1	4000	1488	91	16	6	5	8160	3.7	46	- - -	- -	- - -	
Total-3	15,700						29,651	13.7					12,053.00
M-4	1600	268	22	13	3	5	2368	1.2	38	40' - 24" L	- -	40' - 36"	
M-4	1700	322	25	13	3	5	2516	1.2	38	- - -	- -	- - -	
M-4	4200	2384	133	22	12	5	13,230	5.4	62	- - -	- -	- - -	
L-1	4900	1270	80	17	7	5	10,878	4.8	49	30' R.C. Br.	- -	- - -	
L-1	5000	1806	106	17	7	5	11,100	4.9	49	- - -	- -	- - -	
Total-4	17,400						40,092	17.5					14,163.00
M-5	5100	640	45	13	3	5	7548	3.7	38	(2) 40' - 36" L	- -	15' R.C. Br.	
M-5	4200	1076	69	15	5	5	7770	3.7	44	(3) 40' - 48" L	- -	15' R.C. Br.	
M-5	4000	1380	86	16	6	5	8160	3.7	46	30' R.C. Br.	- -	- - -	



# ENGINEERING AND DESIGN DATA

Area 2 - Indiantown-Stuckey-New Morrisville

Sheet 2 of 4

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-5	1500	1568	96	19	9	5	3885	1.7	55	(2)30' - 30" L/ (2)30' - 24" L	- - -	30' R.C. Br.	
M-5	3000	1884	112	20	10	5	8340	3.5	57	- - -	- - -	- - -	16,186.00
Total-5	17,800						35,703	16.3					
M-6	4000	1132	73	16	6	5	8160	3.7	46	- - -	- - -	- - -	
M-6	1600	1392	86	18	8	5	3856	1.7	52	- - -	- - -	- - -	
M-6	2700	3220	174	26	16	5	10,503	4.2	73	- - -	- - -	- - -	
L-1	3700	164	15	13	3	5	5476	2.7	38	45' R.C. Br. 20' - 24" L	- - -	30' - 30"	
L-1	2000	228	19	13	3	5	2960	1.5	38	- - -	- - -	- - -	
L-2	3300	560	40	13	3	5	4884	2.4	38	- - -	- - -	- - -	
L-2	1000	1292	80	17	7	5	2220	1.0	49	- - -	- - -	- - -	
L-3	3000	704	48	14	4	5	5010	2.4	41	- - -	- - -	- - -	
Total-6	21,300						43,069	19.6					15,107.00
M-7	4800	292	23	13	3	5	7104	3.5	38	40' - 24" L	- - -	40' - 36"	
M-7	7900	840	56	15	5	5	14,615	6.9	44	- - -	- - -	- - -	
M-7	300	940	62	16	6	5	612	0.3	46	- - -	- - -	- - -	
L-1	1800	84	8	13	3	5	2664	1.3	38	- - -	- - -	- - -	
Total-7	14,800						24,995	12.0					9,289.00
M-8	3800	236	20	13	3	5	5624	2.8	38	(2)20' - 24" L/ (2)30' - 30" L	- - -	30' - 36" 30' - 42"	
M-8	1300	296	23	13	3	5	1924	1.0	38	- - -	- - -	- - -	
M-8	1900	412	31	13	3	5	2812	1.4	38	- - -	- - -	- - -	
Total-8	7000						10,360	5.2					4,770.00
M-9	3000	100	10	13	3	5	4440	2.2	38	30' - 24"	30' - 24"	- - -	
M-9	1900	128	12	13	3	5	2812	1.4	38	- - -	- - -	- - -	
Total-9	4900						7252	3.6					2,713.00
M-10	4100	280	23	13	3	5	6068	3.0	38	40' - 36" 40' - 36" L	40' - 36"	- - -	
M-10	1000	532	38	13	3	5	1480	0.7	38	- - -	- - -	- - -	
L-1	3100	200	17	13	3	5	4588	2.3	38	- - -	- - -	- - -	
Total-10	8200						12,136	6.0					4,714.00
M-11	1600	268	22	13	3	5	2368	1.2	38	40' - 40"	40' - 42"	- - -	
M-11	3800	538	39	13	3	5	5624	2.8	38	- - -	- - -	- - -	
Total-11	5400						7992	4.0					3,478.00





# ENGINEERING AND DESIGN DATA

Area 2 - Indiantown - Stuckey - New Morrisville

Sheet 3 of 4

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c. f. s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-12 Total-12	7300 7300	324	25	13	3	5	10,804 10,804	5.4 5.4	38	- - -	- - -	- - -	3,781.00
M-13 M-13 M-13 Total-13	3500 3600 2100 9200	366 716 808	28 49 55	13 14 15	3 4 5	5 5 5	5180 6012 3885 15,077	2.6 2.9 1.8 7.3	38 41 44	40' - 36" 1/2 - - -	- - -	15' R.C. Br. - - -	6,229.00
M-14 M-14 M-14 Total-14	1000 4600 2000 7600	36 256 372	4 21 28	13 13 13	3 3 3	5 5 5	1480 6808 2960 11,248	0.7 3.4 1.5 5.6	38 38 38	30' - 18" 1/2 40' - 36" - - - -	- - - 40' - 36" - - - -	30' - 24" - - - - - - -	4,652.00
M-15 M-15 M-15 Total-15	3100 3000 2700 8800	228 404 588	19 31 42	13 13 13	3 3 3	5 5 5	4588 4440 3996 13,024	2.3 2.2 2.0 6.5	38 38 38	40' - 30" 1/2 (3) 20' - 18" 1/2 - - -	- - - - - - - - -	40' - 36" - 30' - 42" - - - -	5,856.00
M-16 Total-16	5900 5900	404	31	13	3	5	8732 8732	4.3 4.3	38	6' x 6'	- - -	- - -	3,043.00
M-17 M-17 M-17 Total-17	3600 2000 500 6100	128 250 256	12 20 21	13 13 13	3 3 3	5 5 5	5328 2960 740 9028	2.6 1.5 0.4 4.5	38 38 38	50' - 36" - - - - - - -	50' - 36" - - - - - - -	- - - - - - - - -	3,757.00
M-18 M-18 M-18 Total-18	3000 4300 1700 9000	400 704 768	29 49 52	13 14 14	3 4 4	5 5 5	4440 7181 2839 14,460	2.2 3.5 1.4 7.1	38 41 41	40' - 30" 1/2 - - -	- - - - - - - - -	15' R.C. Br. - - -	6,035.00
M-19 M-19 M-19 M-19 M-19 Total-19	2000 2100 4300 800 2200 2000	440 880 1472 2340 2640 4252	33 59 90 130 147 198 3/4	13 15 18 24 24 30	3 5 8 14 14 20	5 5 5 5 5 5	2960 3885 10,363 2816 7744 9260	1.5 1.8 4.5 1.1 3.1 3.6	38 44 52 68 68 84	- - - - - - - - - 30' R.C. Br. - - - - - -	- - - - - - - - - - - - - - - - - -	- - - - - - - - - - - - - - - - - -	



# ENGINEERING AND DESIGN DATA

Area 2 - Indiantown-Stuckey - New Morrisville

Sheet 4 of 4

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c. f. s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
L-1	4600	348	27	13	3	5	6808	3.4	38	- - -	- - -	- - -	
L-2	5300	724	11 2/	13	3	5	7844	3.9	38	None	- - -	15' R.C. Br.	
L-2	4000	1368	56 3/	15	5	5	7400	3.5	41	(2) 40' - 30" L/	- - -	15' R.C. Br.	
L-2	2400	1496	64 3/	16	6	5	4896	2.2	46	- - -	- - -	- - -	
Total -19	29,700						63,976	28.6					23,714.00
M-20		2358											
M-20		4888											
M-20		9308											
M-20	3200	10,128	101 2/	19	9	5	8288	3.6	55	(2) 30' - 30" L/	- - -	30' R.C. Br.	
M-20	4900	11,004	108 2/	20	10	5	13,622	5.7	57	(2) 30' - 24" L/	- - -	30' R.C. Br.	
M-20	1700	11,148	110 2/	20	10	5	4726	2.0	57	None	- - -	- - -	
M-20	3700	19,208	173 2/	26	16	5	14,393	5.7	73	- - -	- - -	- - -	
L-1	5300	412		13	3	5	7844	3.9	38	30' - 24" L/	- - -	30' - 42"	
L-2	1500	196		13	3	5	2220	1.1	38	30' - 24" L/	- - -	30' - 36"	
L-2	4800	536		13	3	5	7104	3.5	38	30' - 18" L/	- - -	30' - 48"	
L-2	7500	864	11 2/	13	3	5	11,100	5.5	38	- - -	- - -	- - -	
L-3	7300	1748	23 2/	13	3	5	10,804	5.4	38	30' - 24" L/	- - -	15' R.C. Br.	
L-3	4000	2272	29 2/	13	3	5	5920	2.9	38	None	- - -	15' R.C. Br.	
L-3		2436								- - -	- - -	- - -	
L-4	11,500	6248	67 2/	16	6	5	23,460	10.6	46	(2) 20' - 18" L/	- - -	15' R.C. Br.	
L-4	2400	6336	68 2/	16	6	5	4896	2.2	46	(2) 20' - 24" L/	- - -	- - -	
L-4	5700	7556	79 2/	17	7	5	12,654	5.6	49	45' C.T. Tres.	- - -	- - -	
Total -20	68,300						134,135	61.2					54,693.00
<p>L/ Remove or abandon (Not included in designed capacity.)</p> <p>2/ Runoff curve used: <math>Q = 10 M^{5/6}</math>.</p> <p>3/ Runoff curve used: <math>Q = 45 M^{5/6}</math> for accumulated area applicable + Q for segment (s) using other runoff coefficients.</p> <p>NOTE: Figure in parentheses in column 11 indicates number of culverts.</p>													

U. S. DEPARTMENT OF AGRICULTURE, SOIL CONSERVATION SERVICE  
USDA-SCS-FORT WORTH, TEX 1970

Work Sheet 3-70 N-R-29076-A





# ENGINEERING AND DESIGN DATA

Area 3 - Nesmith-Rhems - Warsaw

Sheet 1 of 2

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-1	2400	540	39	13	3	5	3552	1.8	38	30' - 30" L/ 30' - 24" L	- - -	30' - 48"	4,750.00
M-1	4700	912	60	14	4	5	7849	3.8	41	- - -	- - -	- - -	
Total-1	7100						11,401	5.6					
M-2	3000	690	48	13	3	5	4440	2.2	38	- - -	- - -	- - -	7,487.00
M-2	5500	1344	83	15	5	5	10,175	4.8	44	- - -	- - -	- - -	
M-2	2800	2600	144	19	9	5	7252	3.1	55	30' R.C. Br.	- - -	- - -	
Total-2	11,300						21,867	10.1					
M-3	10,000	664	47	13	3	5	14,800	7.3	38	(2) 50' - 30"	- - -	50' - 30"	5,860.00
Total-3	10,000						14,800	7.3					
M-4	6000	556	40	13	3	5	8880	4.4	38	15' U.T. Br.	- - -	- - -	
M-4	1200	820	55	15	5	5	2220	1.0	44	(2) 30' - 36" L/ 45' R.C. Br.	- - -	15' R.C. Br.	9,893.00
M-4	6700	1772	105	17	7	5	14,874	6.6	49	- - -	- - -	- - -	
Total-4	13,900						25,974	12.0					
M-5	5300	808	12 2/	13	3	5	7844	3.9	38	- - -	- - -	- - -	4,442
M-5	3300	1208	42 3/	13	3	5	4884	2.4	38	- - -	- - -	- - -	
Total-5	8600						12,728	6.3					
M-6	4200	472	35	13	3	5	6216	3.1	38	12' C.T. Br. L	- - -	- - -	46,551.00
M-6	7800	3000	164	26	16	5	30,342	12.0	73	- - -	- - -	30' R.C. Br.	
M-6	1800	3112	168	26	16	5	7002	2.8	73	- - -	- - -	- - -	
M-6	4900	7122	233 3/	32	22	5	24,500	9.3	90	- - -	- - -	- - -	
L-1	1000	1004	66	16	6	5	2040	0.9	46	(2) 30' - 24" L/ (2) 30' - 24" L	- - -	15' R.C. Br.	
L-1	4600	1396	87	18	8	5	11,086	4.9	52	(2) 30' - 24" L/ (2) 20' - 24" L	- - -	15' R.C. Br.	
L-2	6900	756	12 2/	13	3	5	10,212	5.1	38	(2) 30' - 24" L/ 30' - 30"	- - -	30' - 24"	
L-2	3900	1144	16 2/	13	3	5	5772	2.9	38	20' - 30"	- - -	- - -	
L-2	14,100	3058	37 2/	13	3	5	20,868	10.3	38	12' C.T. Br.	- - -	- - -	
L-2	3600	3522	42 2/	13	3	5	5328	2.6	38	- - -	- - -	- - -	
Total-6	52,800						123,366	53.9					
M-7	2400	208	18	13	3	5	3552	1.8	38	30' - 18" L/ 30' - 30" L	- - -	30' - 36"	
M-7	1200	300	25	13	3	5	1776	0.9	38	30' - 30" L/ 30' - 24"	- - -	30' - 42"	
M-7	2800	436	34	13	3	5	4144	2.1	38	- - -	30' - 24"	30' - 36"	
M-7	2000	472	35	13	3	5	2960	1.5	38	- - -	- - -	- - -	
M-7	400	1703	101	19	9	5	1036	0.4	55	(2) 30' - 24" L/ 30' - 30"	- - -	30' R.C. Br.	



# ENGINEERING AND DESIGN DATA

Area 3 - Ncsmith - Rhems - Warsaw

Sheet 2 of 2

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-7	1100	1737	103	19	9	5	2849	1.2	55	(3) 20' - 30" L	- - -	- - -	
M-7	2500	3319	176	24	14	5	8800	3.6	68	- - -	- - -	30' R.C. Br.	
M-7	3400	3507	186	24	14	5	11,968	4.8	68	- - -	- - -	- - -	
M-7	1800	4103	212	26	16	5	7002	2.8	73	30' - 30" L	- - -	30' R.C. Br.	
L-1	6300	744	51	14	4	5	10,521	5.1	41	16' C.T. Br. L	- - -	15' R.C. Br.	
L-1	1400	786	54	15	5	5	2590	1.2	44	30' - 18" L	- - -	- - -	
L-2	4000	268	22	13	3	5	5920	2.9	38	- - -	- - -	- - -	
L-2	2900	776	53	13	3	5	4292	2.1	38	20' - 30" L	- - -	30' - 36"	
L-2	4800	1042	68	15	5	5	8880	4.2	44	50' - 42" L	- - -	15' R.C. Br.	
L-2	900	1070	69	15	5	5	1665	0.8	44	- - -	- - -	- - -	
L-3	600	130	12	13	3	5	888	0.4	38	20' - 24" L	- - -	30' - 30"	
L-3	4000	374	29	13	3	5	5920	2.9	38	20' - 30" L	- - -	30' - 42"	
L-3	3800	506	37	13	3	5	5624	2.8	38	- - -	- - -	- - -	
Total-7	46,300						90,387	41.5					43,195.00
M-8	4500	308	24	13	3	5	6660	3.3	38	(2) 50' - 30" L	- - -	40' - 42"	
M-8	2000	356	28	13	3	5	2960	1.5	38	(2) 50' - 24" L	- - -	- - -	
M-8	700	792	32	13	3	5	1036	0.5	38	- - -	- - -	- - -	
M-8	2600	1196	76	16	6	5	5304	2.4	46	- - -	- - -	- - -	
M-8	2000	1628	97	17	7	5	4440	2.0	49	- - -	- - -	- - -	
L-1	5300	416	32	13	3	5	7844	3.9	38	- - -	- - -	- - -	
L-2	2000	188	16	13	3	5	2960	1.5	38	30' - 24" L	- - -	30' - 30"	
L-2	1500	276	22	13	3	5	2220	1.1	38	30' - 18" L	- - -	30' - 42"	
L-2	1200	304	24	13	3	5	1776	0.9	38	- - -	- - -	- - -	
L-3	5300	212	18	13	3	5	7844	3.9	38	- - -	- - -	- - -	
Total-8	27,100						43,044	21.0					16,921.00
M-9	6100	652	46	13	3	5	9028	4.5	38	(2) 30' - 24" L	- - -	15' R.C. Br.	
M-9	3200	860	58	14	4	5	5344	2.6	41	30' - 30" L	- - -	- - -	
Total-9	9300						14,372	7.1		18' C.T. Br.	- - -	- - -	6,013.00
M-10	7400	972	64	14	4	5	12,358	5.9	41	15' U.T. Br.	- - -	- - -	
M-10	2000	1220	77	16	6	5	4080	1.8	46	8' x 8'	- - -	- - -	
Total-10	9400						16,438	7.7					5,649.00
1/ Remove or abandon (Not included in designed capacity.) 2/ Runoff curve used: Q = 10 M <sup>5/6</sup> . 3/ Runoff curve used: Q = 45 M <sup>5/6</sup> for accumulated area applicable + Q curve for segment(s) using other runoff coefficients. 4/ Runoff curve used: Q = 118 M <sup>5/6</sup> .													

NOTE: Figure in parenthesis in column 11 indicates number of culverts.  
U.S. DEPARTMENT OF AGRICULTURE, SOIL CONSERVATION SERVICE  
USDA-SCS-FORM NO. 1-72 1-72

Work Sheet 3-70 4-R-29076-A





# ENGINEERING AND DESIGN DATA

## Area 4 - Cades-Roper Crossroads-Cedar Swamp

Sheet 1 of 5

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-1	3800	292	23	13	3	5	5624	2.8	38	10' x 10'	- - -	- - -	
M-1	1200	396	30	13	3	5	1776	0.9	38	(3) 75' - 48"	- - -	- - -	
M-1	8000	1000	66	16	6	5	16,320	7.3	46	- - -	- - -	- - -	
M-1	1300	2112	122	22	12	5	4095	1.7	62	60' R.C. Br.	- - -	- - -	
M-1	4000	2516	141	24	14	5	14,080	5.7	68	(4) 30' - 24" L/ 30' - 18" L/ 30' - 30" L	- - -	30' R.C. Br.	
L-1	7300	324	25	13	3	5	10,804	5.4	38	- - -	- - -	- - -	19,934.00
Total-1	25,600						52,699	23.8					
M-2	4500	352	27	13	3	5	6660	3.3	38	(3) 20' - 18" L/ (2) 30' - 18" L	- - -	40' - 42" 15' R.C. Br.	6,114.00
M-2	3300	584	42	13	3	5	4884	2.4	38	- - -	- - -	- - -	
M-2	400	594	43	13	3	5	592	0.3	38	- - -	- - -	- - -	
Total-2	8200						12,136	6.0					
M-3	12,400	1752	23 2/3	13	3	5	18,352	9.1	38	45' R.C. Br.	- - -	- - -	15,333.00
M-3	6300	2860	94 3/4	18	8	5	15,183	6.7	52	- - -	- - -	- - -	
M-3	600	3436	123 3/4	22	12	5	1890	0.8	62	- - -	- - -	- - -	
L-1	6100	540	39	13	3	5	9028	4.5	38	- - -	- - -	- - -	
Total-3	25,400						44,453	21.1					
M-4	6200	688	49	13	3	5	9176	4.6	38	30' - 30" L/ (2) 40' - 24" L	- - -	15' R.C. Br. 15' R.C. Br.	10,845.00
M-4	4000	1292	81	16	6	5	8160	3.7	46	- - -	- - -	- - -	
M-4	4100	1448	88	16	6	5	8364	3.8	46	- - -	- - -	- - -	
Total-4	14,300						25,700	12.1					
M-5	4500	312	24	13	3	5	6660	3.3	38	40' - 24" L/ 40' - 18" L	- - -	40' - 42"	4,775.00
M-5	3000	372	28	13	3	5	4440	2.2	38	- - -	- - -	- - -	
Total-5	7500						11,100	5.5					
M-6	3800	328	25	13	3	5	5624	2.8	38	30' - 24" L/ 40' - 36" L	- - -	40' - 42" 15' R.C. Br.	6,493.00
M-6	3800	588	42	13	3	5	5624	2.8	38	40' - 30" L	- - -	- - -	
M-6	1300	624	44	13	3	5	1924	1.0	38	- - -	- - -	- - -	
Total-6	8900						13,172	6.6					
M-7	9200	920	60	14	4	5	15,364	7.4	41	(2) 40' - 36" L	- - -	15' R.C. Br.	11,810.00
M-7	7900	1412	87	16	6	5	16,116	7.3	46	- - -	- - -	- - -	
Total-7	17,100						31,480	14.7					



# ENGINEERING AND DESIGN DATA

Area 4 - Cades-Roper Crossroads-Cedar Swamp

Sheet 2 of 5

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-8	7900	452	33	13	3	5	11,692	5.8	38	40' - 30" L	- - -	40' - 42"	6,664.00
M-8	3300	536	39	13	3	5	4884	2.4	38	- - -	- - -	- - -	
Total-8	11,200						16,576	8.2					
M-9	3300	480	35	13	3	5	4884	2.4	38	40' - 24"	40' - 24"	40' - 36"	39,277.00
M-9	4500	1160	73	16	6	5	9180	4.1	46	- - -	- - -	- - -	
M-9	6900	1760	104	19	9	5	17,871	7.8	55	- - -	- - -	- - -	
M-9	2500	3292	175	28	18	5	10,650	4.1	78	40' C.T. Br.	- - -	- - -	
M-9	800	3320	176	28	18	5	3408	1.3	78	- - -	- - -	- - -	
M-9	4200	4052	209	30	20	5	19,446	7.5	84	- - -	- - -	- - -	
L-1	2800	432	33	13	3	5	4144	2.1	38	(2) 30' - 24" L	- - -	30' - 42"	
L-1	3200	868	58	15	5	5	5920	2.8	44	(2) 30' - 30" L	- - -	15' R.C. Br.	
L-1	4500	1220	77	17	7	5	9990	4.4	49	(2) 30' - 30" L	- - -	15' R.C. Br.	
L-1	800	1232	78	17	7	5	1776	0.8	49	- - -	- - -	- - -	
L-2	4000	280	23	13	3	5	5920	2.9	38	40' - 24" L	- - -	40' - 36"	
L-2	3500	416	31	13	3	5	5180	2.6	38	20' - 24" L	- - -	30' - 42"	
L-2	2500	468	34	13	3	5	3700	1.8	38	- - -	- - -	- - -	
Total-9	43,500						102,069	44.6					
M-10	2600	320	25	13	3	5	3848	1.9	38	30' - 24"	30' - 24"	30' - 30"	18,769.00
M-10	4800	692	48	14	4	5	8016	3.9	41	30' - 18" L	- - -	15' R.C. Br.	
M-10	5800	1728	103	19	9	5	15,022	6.5	55	30' - 24" L	- - -	- - -	
M-10	4100	2896	159	26	16	5	15,949	6.3	73	30' - 18" L	- - -	- - -	
L-1	5300	604	43	13	3	5	7844	3.9	38	30' U.T. Br.	- - -	- - -	
Total-10	22,600						50,679	22.5					
M-11	6600	568	41	13	3	5	9768	4.8	38	(2) 20' - 24" L	- - -	30' - 48"	45,508.00
M-11	3000	1600	97	19	9	5	7770	3.4	55	30' R.C. Br.	- - -	- - -	
M-11	8500	3284	177	28	18	5	36,210	14.0	78	(3) 30' - 18" L	- - -	30' R.C. Br.	
M-11	3300	3696	196	30	20	5	15,279	5.9	84	30' - 24" L	- - -	- - -	
M-11	7700	5468	269	36	26	5	44,198	16.4	105	35' U.T. Br.	- - -	- - -	
L-1	4500	476	35	13	3	5	6660	3.3	38	30' - 30" L	- - -	30' - 48"	
L-1	3800	848	57	15	5	5	7030	3.3	44	- - -	- - -	- - -	
Total-11	37,400						126,915	51.1					
M-12	2100	168	15	13	3	5	3108	1.5	38	(2) 30' - 18" L	- - -	30' - 30"	4,812.00
M-12	1500	288	23	13	3	5	2220	1.1	38	30' - 30" L	- - -	30' - 36"	
M-12	4000	536	39	13	3	5	5920	2.9	38	- - -	- - -	- - -	
Total-12	7600						11,248	5.5					

Work Sheet 3-70 U-R-29076-A

U. S. DEPARTMENT OF AGRICULTURE, SOIL CONSERVATION SERVICE  
WASHINGTON, D. C. 20250





# ENGINEERING AND DESIGN DATA

## Area 4 - Cades - Roper Crossroads-Cedar Swamp

Sheet 3 of 5

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-13 M-13 Total-13	3200 1700 4900	144 184 328	13 16 29	13 13 14	3 3 4	5 5 5	4736 2516 7252	2.4 1.2 3.6	38 38 41	40' - 30" - - - - - -	40' - 30" - - - - - -	- - - - - - - - -	2,973.00
M-14 Total-14	5300 5300	308	24	13	3	5	7844 7844	3.9 3.9	38	- - -	- - -	- - -	2,741.00
M-15 M-15 M-15 Total-15	3400 4100 2400 9900	256 556 632	21 40 45	13 13 13	3 3 3	5 5 5	5032 6068 3552 14,652	2.5 3.0 1.8 7.3	38 38 38	40' - 36" 40' - 30" L/ - - -	40' - 36" - - - - - -	15' R.C. Br. - - - - - -	6,603.00
M-16 M-16 Total-16	1400 4500 5900	256 392	21 30	13 13	3 3	5 5	2072 6660 8732	1.0 3.3 4.3	38 38	30' - 30" L/ - - -	- - - - - -	30' - 36" - - -	3,523.00
M-17 M-17 M-17 M-17 L-1 L-1 Total-17	2400 4000 3000 1200 2800 5400 1200 20,000	756 1260 1464 1504 1936 276 292	52 79 89 92 112 22 24	14 17 18 18 18 13 13	4 7 8 8 8 3 3	5 5 5 5 5 5 5	4008 8880 7230 2892 6748 7992 1776 39,526	1.9 3.9 3.2 1.3 3.0 4.0 0.9 18.2	41 49 52 52 52 38 38	- - - - - - 30' - 30" L/ - - - - - - 30' - 30" L/ - - -	- -	15' R.C. Br. - - - - - - - - - 30' - 36" - - -	15,001.00
M-18 Total-18	4000 4000	328	25	13	3	5	5920 5920	2.9 2.9	38	(2) 30' - 18" L/ - - -	- - -	30' - 42"	2,720.00
M-19 M-19 M-19 Total-19	8700 1200 4600 14,500	376 444 672	29 33 47	13 13 14	3 3 4	5 5 5	12,876 1776 7682 22,334	6.4 0.9 3.7 11.0	38 38 41	30' - 24" L/ 40' - 30" L/ - - -	- - - - - - - - -	30' - 42" 40' - 42" - - -	9,323.00
M-20 M-20 Total-20	2900 5800 8700	708 1068	49 68	14 16	4 6	5 5	4843 11,832 16,675	2.3 5.3 7.6	41 46	30' - 24" L/ - - -	- - - - - -	15' R.C. Br. - - -	6,689.00

U. S. DEPARTMENT OF AGRICULTURE, SOIL CONSERVATION SERVICE  
USDA-SCS-FORT WORTH, TEX. 1970

Work Sheet 3-70 W-R-29076-A



# ENGINEERING AND DESIGN DATA

## Area 4 - Cades-Roper Crossroads-Cedar Swamp

Sheet 4 of 5

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-21	3600	416	31	13	3	5	5328	2.6	38	(2) 30' - 24" 1/2	- - -	30' - 42"	4,956.00
M-21	1600	462	34	13	3	5	2368	1.2	38	20' - 30" 1/2	- - -	30' - 48"	
M-21	1600	508	37	13	3	5	2368	1.2	38	- - -	- - -	- - -	
Total-21	6800						10,064	5.0					
M-22	4200	500	37	13	3	5	6216	3.1	38	40' - 24" 1/2	- - -	15' R.C. Br.	27,442.00
M-22	10,200	1544	94	16	6	5	20,808	9.4	46	30' C.T. Br.	- - -	- - -	
M-22	7100	2612	147	22	12	5	22,365	9.1	62	- - -	- - -	- - -	
Total-22	28,500	4620	235	28	18	5	79,209	33.2	78	45' R.C. Br.	- - -	- - -	
M-23	5800	404	31	13	3	5	8584	4.3	38	40' - 36" 1/2	- - -	40' - 42"	6,419.00
Total-23	10,700	716	49	13	3	5	15,836	7.9	38	- - -	- - -	- - -	
M-24	2900	550	40	13	3	5	4292	2.1	38	- - -	- - -	- - -	6,651.00
M-24	4400	1080	69	16	6	5	8976	4.0	46	45' R.C. Br.	- - -	- - -	
M-24	2800	1256	78	17	7	5	6216	2.8	49	- - -	- - -	- - -	
Total-24	10,100						19,484	8.9					
M-25	4000	348	27	13	3	5	5920	2.9	38	30' - 24" 1/2	- - -	30' - 42"	6,629.00
M-25	300	600	42	13	3	5	444	0.2	38	30' - 30" 1/2	- - -	15' R.C. Br.	
M-25	2100	752	51	13	3	5	3108	1.5	38	40' - 48" 1/2	- - -	15' R.C. Br.	
Total-25	7700	780	52	13	3	5	1924	1.0	38	- - -	- - -	- - -	
M-26	3600	272	22	13	3	5	5328	2.6	38	(2) 30' - 18" 1/2	- - -	30' - 36"	23,744.00
M-26	2900	480	35	13	3	5	4292	2.1	38	None	- - -	30' - 48"	
M-26	7300	1160	74	16	6	5	14,892	6.7	46	- - -	- - -	- - -	
M-26	5100	1488	90	18	8	5	12,291	5.4	52	40' - 30" 1/2	- - -	15' R.C. Br.	
M-26	2800	2064	119	22	12	5	8820	3.6	62	- - -	- - -	- - -	23,744.00
L-1	2900	228	19	13	3	5	4292	2.1	38	30' - 15" 1/2	- - -	30' - 36"	
L-1	6500	464	34	13	3	5	9620	4.8	38	30' - 30" 1/2	- - -	30' - 36"	
Total-26	31,100						59,536	27.3		30' - 24"	30' - 24"		





# ENGINEERING AND DESIGN DATA

Area 4 - Cades - Roper Crossroads-Cedar Swamp

Sheet 5 of 5

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-27	5300	576	41	13	3	5	7844	3.9	38	- - -	- - -	- - -	
M-27	6300	1288	80	17	7	5	13,986	6.2	49	(2) 5' x 5'	- - -	- - -	
M-27	7100	1584	96	19	9	5	18,389	8.0	55	- - -	- - -	- - -	
Total-27	18,700						40,219	18.1					13,675.00
1/ Remove or abandon (Not Included in designed capacity.)													
2/ Runoff curve used: Q=10 M 5/6.													
3/ Runoff curve used: Q=45 M 5/6 for accumulated area applicable + Q curve for segment (s) using other runoff coefficients.													
NOTE: Figure in parenthesis in column 11 indicates number of culverts.													



# ENGINEERING AND DESIGN DATA

Area 5 - Millwood - Trio - Sutton's

Sheet 1 of 4

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-1 Total-1	6600 6600	660	46	13	3	5	9768 9768	4.8 4.8	38	40' - 60"	- - -	- - -	3,402.00
M-2 Total-2	6400 6400	440	33	13	3	5	9472 9472	4.7 4.7	38	- - -	- - -	- - -	2,368.00
M-3 Total-3	5000 1000 2300 8300	660 1168 1252	43 75 78	13 15 17	3 5 7	5	7400 1850 5106 14,356	3.7 0.9 2.3 6.9	38 44 49	(2) 6' x 6'	- - - - - - - - -	- - - - - - - - -	4,969.00
M-4 Total-4	4400 400 4800	480 492	35 36	13 13	3 3	5	6512 592 7104	3.2 0.3 3.5	38 38	(2) 40' - 30" 1/2	- - - - - -	15' R.C. Br. - - -	3,476.00
M-5 Total-5	5500 1300 6800	272 328	22 26	13 13	3 3	5	8140 1924 10,064	4.0 1.0 5.0	38 38	40' - 30" 1/2	- - - - - -	40' - 36" - - -	4,156.00
M-6 Total-6	3400 1700 1500 6600	184 220 260	16 19 21	13 13 13	3 3 3	5	5032 2516 2220 9768	2.5 1.2 1.1 4.8	38 38 38	40' - 24" 1/2	- - - - - - - - -	40' - 30" - - - - - -	3,962.00
M-7 Total-7	3800 1500 3400 2900 600 1800 6600 4000 24,600	800 864 1024 1468 1840 1912 320 356	54 58 67 90 109 112 25 28	13 15 16 18 20 20 13 13	3 5 6 8 10 10 3 3	5	5624 2775 6936 6989 1668 5004 5920 44,684	2.8 1.3 3.1 3.1 0.7 2.1 4.8 20.8	38 44 46 52 57 57 38 38	30' - 30" 1/2 30' - 18" 1/2 30' - 30" 1/2 30' - 18" 1/2 (2) 30' - 36" 30' - 24"	- -	15' R.C. Br. 15' R.C. Br. - - - - - - 30' R.C. Br. - - - - - - - - -	19,331.00





# ENGINEERING AND DESIGN DATA

Area 5 - Millwood - Trio - Sutton's

Sheet 2 of 4

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-8	2800	400	30	13	3	5	4144	2.1	38	40' - 48"	- - -	- - -	
M-8	2300	464	34	13	3	5	3404	1.7	38	- - -	- - -	- - -	
M-8	4700	1344	84	16	6	5	9588	4.3	46	(2) 6' x 6'	- - -	- - -	
M-8	3500	1508	92	16	6	5	7140	3.2	46	- - -	- - -	- - -	
M-8	4200	3330	177	24	14	5	15,840	6.0	68	- - -	- - -	- - -	
M-8	3200	4112	212	30	20	5	14,816	5.7	84	- - -	- - -	- - -	
L-1	4500	440	33	13	3	5	6660	3.3	38	- - -	- - -	- - -	
L-2	1200	168	15	13	3	5	1776	0.9	38	None	- - -	- - -	
L-2	5500	816	55	13	3	5	8140	4.0	38	- - -	- - -	- - -	
L-2		1152					Present canal as constructed is considered adequate.						
L-2		1432					Present canal as constructed is considered adequate.						
Total-8	31,900						71,508	31.2					24,537.00
M-9	3600	176	15	13	3	5	5328	2.6	38	30' - 24" L	- - -	30' - 30"	
M-9	2400	352	27	13	3	5	3552	1.8	38	30' - 24" L	- - -	30' - 42"	
M-9	2800	500	37	13	3	5	4144	2.1	38	(2) 30' - 18" L	- - -	- - -	5,636.00
Total-9	8800						13,024	6.5					
M-10	7500	672	46	13	3	5	11,100	5.5	38	- - -	- - -	- - -	
M-10	3800	1008	64	14	4	5	6346	3.1	41	(2) 4' x 8'	- - -	- - -	
M-10	2000	1128	72	16	6	5	4080	1.8	46	15' U.T. Br. L	- - -	15' R.C. Br.	
M-10	3000	1272	79	17	7	5	6660	3.0	49	- - -	- - -	- - -	10,726.00
Total-10	16,300						28,186	13.4					
M-11	5800	640	45	13	3	5	8584	4.3	38	- - -	- - -	- - -	
M-11	2800	968	63	14	4	5	4676	2.2	41	- - -	- - -	- - -	
M-11	1500	1028	67	15	5	5	2775	1.3	44	- - -	- - -	- - -	5,569.00
Total-11	10,100						16,035	7.8					
M-12	3000	148	13	13	3	5	4440	2.2	38	30' - 18" L	- - -	30' - 30"	
M-12	1300	208	17	13	3	5	1924	1.0	38	(2) 40' - 24" L	- - -	- - -	
M-12	1500	328	25	13	3	5	2220	1.1	38	- - -	- - -	- - -	3,906.00
Total-12	5800						8584	4.3					
M-13	8100	736	51	13	3	5	11,988	6.0	38	30' R.C. Br.	- - -	- - -	
M-13	3300	1000	66	14	4	5	5511	2.7	41	- - -	- - -	- - -	
M-13	4000	1904	111	18	8	5	9640	4.2	52	(2) 40' - 36" L	- - -	30' R.C. Br.	
M-13	2000	1980	114	20	10	5	5560	2.3	57	- - -	- - -	- - -	13,215.00
Total-13	17,400						32,699	15.2					



# ENGINEERING AND DESIGN DATA

Area 5 - Millwood - Trio - Sutton's

Sheet 3 of 4

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-14	4200	688	47	13	3	5	6216	3.1	38	(2) 4' x 4'	- - -	- - -	10,539.00
M-14	7300	1220	77	16	6	5	14,892	6.7	46	- - -	- - -	- - -	
M-14	4400	1372	85	17	7	5	9768	4.3	49	- - -	- - -	- - -	
Total-14	15,900						30,876	14.1					
M-15	3200	296	23	13	3	5	4736	2.4	38	40' - 18" L	- - -	40' - 42"	3,413.00
M-15	1700	360	28	13	3	5	2516	1.2	38	- - -	- - -	- - -	
Total-15	4900						7252	3.6					
M-16	5300	572	40	13	3	5	7844	3.9	38	- - -	- - -	- - -	3,545.00
M-16	1400	876	58	14	3	5	2338	1.1	41	- - -	- - -	- - -	
Total-16	6700						10,182	5.0					
M-17	1300	800	54	15	5	5	2405	1.1	44	(3) 40' - 48" L	- - -	15' R.C. Br.	7,714.00
M-17	500	940	62	16	6	5	1020	0.5	46	(2) 40' - 36" L	- - -	15' R.C. Br.	
M-17	3000	1390	86	16	6	5	6120	2.8	46	- - -	- - -	- - -	
M-17	3000	1840	109	18	8	5	7230	3.2	52	- - -	- - -	- - -	
Total-17	7800						16,775	7.6					
M-18	1100	1768	23 2/	13	3	5	16,280	8.0	38	(2) 40' - 24" L	- - -	15' R.C. Br.	47,113.00
M-18	3900	2328	90 3/	13	3	5	5772	2.9	38	- - -	- - -	- - -	
M-18	8000	3252	90 3/	18	8	5	19,280	8.4	52	15' R.C. Br.	- - -	15' R.C. Br.	
M-18	1200	3456	102 3/	19	9	5	3108	1.3	55	(3) 40' - 36" L	- - -	15' R.C. Br.	
M-18	2000	3812	120 3/	22	12	5	6300	2.6	62	- - -	- - -	- - -	
M-18	7500	5344	195 3/	24	14	5	26,400	10.7	68	- - -	- - -	- - -	
M-18	4700	5984	223 3/	28	18	5	20,022	7.8	78	- - -	- - -	- - -	
M-18	3400	6956	265 3/	30	20	5	15,742	6.1	84	- - -	- - -	- - -	
L-1	6100	564	40	13	3	5	9028	4.5	38	(2) 30' - 18" L	- - -	30' - 48"	
L-1	600	580	41	13	3	5	888	0.4	38	- - -	- - -	- - -	
L-2	4200	468	34	13	3	5	6216	3.1	38	- - -	- - -	- - -	
L-2	2200	556	40	13	3	5	3256	1.6	38	30' - 30" L	- - -	30' - 48"	
L-2		660							38	- - -	- - -	- - -	
Total-18	54,800						Present branch run is considered adequate. 132,292	57.4					
M-19	5500	502	36	13	3	5	8140	4.0	38	- - -	- - -	- - -	7,276.00
M-19	5500	1004	66	14	4	5	9185	4.4	41	- - -	- - -	- - -	
M-19	2000	1108	71	15	5	5	3700	1.7	44	- - -	- - -	- - -	
Total-19	13,000						21,025	10.1					



# ENGINEERING AND DESIGN DATA

Area 5 - Millwood - Trio - Sutton's

Sheet 4 of 4

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-20	4000	600	42	13	3	5	5920	2.9	38	- - -	- - -	- - -	
M-20	2300	980	64	14	4	5	3841	1.9	41	- - -	- - -	- - -	
M-20	2300	1364	85	16	6	5	4692	2.1	46	30' - 30" 1/2	- - -	15' R.C. Br.	
M-20	3400	1532	93	18	8	5	8194	3.6	52	30' - 24" 1/2	- - -	- - -	
M-20	7000	4304	221	26	16	5	27,230	10.8	73	45' R.C. Br.	- - -	- - -	
L-1	3200	1600	97	17	7	5	7104	3.2	49	(2) 30' - 24" 1/2	- - -	30' R.C. Br.	
L-1	2200	1664	100	17	7	5	4884	2.2	49	- - -	- - -	- - -	
Total-20	24,400						61,865	26.7					23,806.00
<p>1/ Remove or abandon (Not included in designed capacity.)</p> <p>2/ Runoff curve used: <math>Q = 10 M^{5/6}</math>.</p> <p>3/ Runoff curve used: <math>Q = 45 M^{5/6}</math> for accumulated area applicable + Q curve for segment(s) using other runoff coefficients.</p> <p>NOTE: Figure in parenthesis in column 11 indicates number of culverts.</p>													





# ENGINEERING AND DESIGN DATA

**Area 6 • Bloomingvale • Earle • Wee Tee**

Sheet 1 of 4

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP- WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-1	4600	528	39	13	3	5	6808	3.4	38	40' - 24" $\sqrt{1}$	- - -	15' R.C. Br.	13,267.00
M-1	3800	900	60	14	4	5	6346	3.1	41	(2) 30' - 24" $\sqrt{1}$	- - -	15' R.C. Br.	
M-1	2600	1244	78	16	6	5	5304	2.4	46	(2) 30' - 24" $\sqrt{1}$	- - -	15' R.C. Br.	
M-1	3200	1424	88	16	6	5	6528	2.9	46	(2) 30' - 18" $\sqrt{1}$	- - -	- - -	
M-1 Total-1	2200 16,400	1692	100	17	7	5	4884 29,870	2.2 14.0	49	7' x 7' - - -	- - -	- - -	
M-2 Total-2	4600 4600	592	42	13	3	5	6808 6808	3.4 3.4	38	50' - 24" $\sqrt{1}$	- - -	15' R.C. Br.	3,382.00
M-3	3400	532	39	13	3	5	5032	2.5	38	40' - 36" $\sqrt{1}$	- - -	15' R.C. Br.	19,501.00
M-3	4000	676	47	14	4	5	6680	3.2	41	- - -	- - -	- - -	
M-3	7100	1780	106	17	7	5	15,762	7.0	49	- - -	- - -	- - -	
M-3	600	2496	140	20	10	5	1668	0.7	57	- - -	- - -	- - -	
L-1	2600	744	51	13	3	5	3848	1.9	38	- - -	- - -	- - -	
L-2	2100	412	31	13	3	5	3108	1.5	38	(2) 20' - 24" $\sqrt{1}$	- - -	30' - 48"	7,377.00
L-2	4100	644	45	13	3	5	6068	3.0	38	- - -	- - -	- - -	
Total-3	23,900						42,166	19.8					
M-4	1700	164	15	13	3	5	2516	1.2	38	- - -	- - -	- - -	
M-4	3200	960	63	16	6	5	6528	2.9	46	(3) 6' x 6'	- - -	- - -	
L-1	5900	603	42	13	3	5	8732	4.3	38	30' - 18" $\sqrt{1}$	- - -	30' - 48"	3,013.00
L-1	900	612	43	13	3	5	1332	0.7	38	- - -	- - -	- - -	
Total-4	11,700						19,108	9.1					
M-5	900	240	19	13	3	5	1332	0.7	38	20' - 18" $\sqrt{1}$	- - -	30' - 36"	
M-5 Total-5	4000 4900	384	29	13	3	5	5920 7252	2.9 3.6	38	(2) 5' x 5'	- - -	- - -	
M-6	2100	92	9	13	3	5	3108	1.5	38	40' - 24"	40' - 24"	- - -	3,642.00
M-6	4500	388	30	13	3	5	6660	3.3	38	- - -	- - -	- - -	
Total-6	6600						9768	4.8					
M-7	6100	1260	17 $\frac{2}{3}$	13	3	5	9028	4.5	38	- - -	- - -	15' R.C. Br.	
M-7	4800	2140	76 $\frac{3}{4}$	16	6	5	9792	4.4	46	(2) 30' - 30" $\sqrt{1}$	- - -	15' R.C. Br.	
M-7	4000	2932	117 $\frac{3}{4}$	22	12	5	12,600	5.1	62	30' R.C. Br.	- - -	- - -	17,785.00
M-7	4000	3732	156	26	16	5	15,560	6.2	73	60' R.C. Br.	- - -	- - -	
Total-7	18,900						46,980	20.2					

U. S. DEPARTMENT OF AGRICULTURE, SOIL CONSERVATION SERVICE  
USDA-SCS-FORT WORTH, TEX. 1970

Work Sheet 3-70

4-R-29076-A



# ENGINEERING AND DESIGN DATA

Area 6 - Bloomingdale - Earle - Wee Tee

Sheet 2 of 4

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c. f. s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-8	4500	404	31	13	3	5	6660	3.3	38	- - -	- - -	- - -	11,265.00
M-8	1300	1504	92	16	6	5	2652	1.2	46	- - -	- - -	- - -	
L-1	3800	564	41	13	3	5	5624	2.8	38	(2) 40' - 24" L/	- - -	15' R.C. Br.	
L-1	1300	672	47	14	4	5	2171	1.0	41	(2) 40' - 30" L/	- - -	15' R.C. Br.	
L-1	3300	1004	66	16	6	5	6732	3.0	46	4' x 4'	- - -	- - -	
L-1	1500	1060	69	16	6	5	3060	1.4	46	15' U.T. Br.	- - -	- - -	6,673.00
Total-8	15,700						26,899	12.7					
M-9	3600	164	15	13	3	5	5328	2.6	38	30' - 24" L/	- - -	30' - 30"	
M-9	4000	292	23	13	3	5	5920	2.9	38	40' - 24" L/	- - -	40' - 36"	
M-9	3300	460	34	13	3	5	4884	2.4	38	40' - 24" L/	- - -	- - -	
Total-9	10,900						16,132	7.9					
M-10	2800	420	32	13	3	5	4144	2.1	38	- - -	- - -	- - -	127,127.00
M-10	2000	1372	85	17	7	5	4440	2.0	49	- - -	- - -	- - -	
M-10	3600	1916	112	20	10	5	10,008	4.2	57	30' R.C. Br.	- - -	- - -	
M-10	6000	2344	133	22	12	5	18,900	7.7	62	- - -	- - -	- - -	
M-10	3100	4088	210	30	20	5	14,353	5.6	84	20' - 24" L/	- - -	30' R.C. Br.	
M-10	900	4180	215	32	22	5	4500	1.7	89	(2) 20' - 18" L/	- - -	30' R.C. Br.	
M-10	3200	4460	228	32	22	5	16,000	6.1	89	30' - 30" L/	- - -	30' R.C. Br.	
M-10	800	4520	229	32	22	5	4000	1.5	89	- - -	- - -	- - -	
M-10	3600	10,208	455	45	35	5	26,665	9.8	124	45' R.C. Br.	- - -	- - -	
M-10	4000	10,748	470	45	35	5	29,628	10.8	124	45' R.C. Br.	- - -	- - -	
L-1	11,200	776	52	14	4	5	18,704	9.0	41	40' - 24" L/	- - -	15' R.C. Br.	
L-1	1200	808	56	15	5	5	2220	1.0	44	- - -	- - -	- - -	
L-2	3900	208	18	13	3	5	5772	2.9	38	- - -	- - -	- - -	
L-3	3900	572	41	13	3	5	5772	2.9	38	40' - 24" L/	- - -	15' R.C. Br.	
L-3	1800	1144	73	16	6	5	3672	1.7	46	- - -	- - -	- - -	
L-3	4800	1460	89	18	8	5	11,568	5.1	52	40' - 24" L/	- - -	40' - 36"	
L-4	2900	208	18	13	3	5	4292	2.1	38	- - -	- - -	15' R.C. Br.	
L-4	10,600	1148	73	16	6	5	21,624	9.8	46	30' R.C. Br.	- - -	- - -	
L-4	9900	2136	124	22	12	5	31,185	12.7	62	(5) 40' - 30" L/	- - -	30' R.C. Br.	
L-4	12,700	3904	203	30	20	5	58,801	22.7	84	40' - 36" L/	- - -	- - -	
L-4	7600	5132	257	36	26	5	43,624	16.2	99	Washed out	- - -	45' R.C. Br.	127,127.00
Total-10	100,500						339,872	137.6					
M-11	7600	664	10 2/	13	3	5	11,248	5.6	38	- - -	- - -	- - -	
M-11	4000	3520	42 2/	13	3	5	5920	2.9	38	- - -	- - -	- - -	
M-11	3500	5292	147 3/	22	12	5	11,025	4.5	62	30' R.C. Br.	- - -	- - -	





# ENGINEERING AND DESIGN DATA

Area 6- Bloomingdale - Earle - Wee Tee

Sheet 3 of 4

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-11	2600	5544	159 3/4	22	12	5	8190	3.3	62	(2)30' - 36" L/ 30' - 24" L/ 30' - 30" L/ (3)30' - 18" L	- - - - - - - - - - - -	- - - - - - 15' R.C. Br. - - -	
M-11	1300	5608	163 3/4	22	12	5	4095	1.7	62	- - -	- - -	- - -	
M-11	2000	6728	214 3/4	30	20	5	9260	3.6	84	- - -	- - -	- - -	
L-1	7200	972	14 2/3	13	3	5	10,656	5.3	38	- - -	- - -	- - -	
L-1	2800	1388	19 2/3	13	3	5	4144	2.1	38	30' - 18" L	- - -	15' R.C. Br.	
L-1	8800	2596	32 2/3	13	3	5	13,024	6.5	38	- - -	- - -	15' R.C. Br.	
L-2	5300	560	40	13	3	5	7844	3.9	38	30' - 30" L	- - -	30' - 48"	
L-2	3600	970	64	14	4	5	6012	2.9	41	- - -	- - -	- - -	
L-2	7000	1380	86	16	6	5	14,280	6.4	46	- - -	- - -	- - -	
L-3	4500	452	34	13	3	5	6660	3.3	38	20' - 30" L/ 20' - 24" L/ 20' - 18" L	- - - - - - - - -	30' - 42"	
L-3	1900	644	45	14	4	5	3173	1.5	41	20' - 24" L/ 20' - 18" L	- - - - - -	15' R.C. Br.	
L-3	800	744	52	14	4	5	1336	0.6	41	20' - 24" L/ 20' - 30" L	- - - - - -	15' R.C. Br.	
L-3	2100	944	62	16	6	5	4284	1.9	46	40' - 30" L/ 40' - 36" L	- - - - - -	15' R.C. Br.	
L-3	2100	1060	69	16	6	5	4284	1.9	46	40' - 48" L	- - -	15' R.C. Br.	
L-3	700	1072	70	16	6	5	1428	0.6	46	- - -	- - -	- - -	
Total-11	67,800						126,863	58.5	46				51,856.00
M-12	3800	748	51	14	4	5	6346	3.1	41	- - -	- - -	- - -	
M-12	3500	1800	77 3/4	17	7	5	7770	3.5	49	(2)30' - 30" L/ (4)30' - 24" L/ (2)30' - 18" L	- - - - - - - - -	15' R.C. Br.	
M-12	500	2264	83 3/4	17	7	5	1110	0.5	49	30' - 30" L	- - -	15' R.C. Br.	
M-12	2100	2460	95 3/4	18	8	5	5061	2.2	52	- - -	- - -	- - -	
M-12	1100	2528	98 3/4	19	9	5	2849	1.2	55	(3)30' - 24" L/ (3)30' - 18" L	- - - - - -	15' R.C. Br.	
M-12	500	2900	118 3/4	22	12	5	1575	0.6	62	- - -	- - -	- - -	
M-12	5500	3688	155 3/4	24	14	5	19,360	7.8	68	- - -	- - -	- - -	
M-12	2300	5200	224 3/4	28	18	5	9798	3.8	78	30' U.T. Br.	- - -	- - -	
M-12	2800	5320	228 3/4	28	18	5	11,928	4.6	78	- - -	- - -	- - -	
M-12	900	8360	272 3/4	36	26	5	5160	1.9	99	60' R.C. Br.	- - -	- - -	
L-1	1500	180	3 2/3	13	3	5	2220	1.1	38	20' - 18" L	- - -	30' - 30"	
L-1	4800	704	11 2/3	13	3	5	7104	3.5	38	(2)40' - 24" L	- - -	15' R.C. Br.	
L-1	2400	808	12 2/3	13	3	5	3552	1.8	38	- - -	- - -	- - -	
L-2	5800	336	6 2/3	13	3	5	8584	4.3	38	(2)40' - 24" L/ 40' - 24" L	- - - - - -	40' - 42"	
L-2	3400	452	7 2/3	13	3	5	5032	2.5	38	- - -	- - -	- - -	
L-3	4000	348	27	13	3	5	5920	2.9	38	40' - 30" L	- - -	40' - 42"	



# ENGINEERING AND DESIGN DATA

Area 6- Bloomingdale - Earle - Wee Tec

Sheet 4 of 4

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
L-3	1300	360	28	13	3	5	1924	1.0	38	- - -	- - -	- - -	52,534.00
L-4	2100	1052	67	16	6	5	4284	1.9	46	(2) 40' - 36" L/	- - -	15' R.C. Br.	
L-4	2800	1272	79	16	6	5	5712	2.6	46	- - -	- - -	- - -	
L-5	1200	2452	24 2/	13	3	5	1776	0.9	38	- - -	- - -	15' R.C. Br.	
L-5	5400	2860	35 2/	13	3	5	7992	4.0	38	(2) 30' - 24" L/	- - -	15' R.C. Br.	
L-5	2000	2932	42 3/	13	3	5	2960	1.5	38	- - -	- - -	- - -	52,534.00
Total-12	59,700						128,017	57.2					
M-13	700	268	22	13	3	5	1036	0.5	38	- - -	- - -	30' - 30"	12,532.00
M-13	4900	660	46	14	4	5	8183	3.9	41	- - -	- - -	- - -	
M-13	4900	1052	68	16	6	5	9996	4.5	46	30' - 24" L/	- - -	15' R.C. Br.	
M-13	4700	1604	98	17	7	5	10,434	4.6	49	30' - 18" L/	- - -	- - -	
Total-13	15,200						29,649	13.5		(3) 40' - 30" L/	- - -	15' R.C. Br.	
M-14	9900	1696	23 2/	13	3	5	14,652	7.3	38	- - -	- - -	- - -	21,626.00
M-14	5000	2296	65 3/	16	6	5	10,200	4.6	46	- - -	- - -	- - -	
M-14	4900	2908	100 3/	19	9	5	12,691	5.5	55	- - -	- - -	- - -	
M-14	1600	4696	187 3/	28	18	5	6816	2.6	78	- - -	- - -	- - -	
L-1	6200	860	58	14	4	5	10,354	5.0	41	30' - 30" L/	- - -	15' R.C. Br.	
L-1	2800	1180	75	16	6	5	5712	2.6	46	- - -	- - -	- - -	21,626.00
Total-14	30,400						60,425	27.6					
1/ Remove or abandon (Not included in designed capacity.)													
2/ Runoff curve used: Q=10 M 5/6.													
3/ Runoff curve used: Q=45 M 5/6 for accumulated area applicable + Q curve for segment(s) using other runoff coefficients.													
NOTE: Figure in parentheses in column 11 indicates number of culverts.													



# ENGINEERING AND DESIGN DATA

Area 7 - Kingstree - Cades - Moores

Sheet 1 of 3

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-1	500	16	1	13	3	5	740	0.4	38	30' - 18" L/ 30' - 24"	- - -	30' - 24"	2,822.00
M-1	1300	60	6	13	3	5	1924	1.0	38	- - -	- - -	- - -	
M-1	2800	108	10	13	3	5	4144	2.1	38	- - -	- - -	- - -	
Total-1	4600						6808	3.5					
M-2	4600	2100	121	19	9	5	11,914	5.2	54	(3) 40' - 48" L/ 45' C.T. Br.	- - -	15' R.C. Br.	11,455.00
M-2	2200	2502	141	20	10	5	6116	2.6	57	- - -	- - -	- - -	
M-2	2200	2904	159	22	12	5	6930	2.8	62	- - -	- - -	- - -	
M-2	2000	2972	162	22	12	5	6300	2.6	62	- - -	- - -	- - -	
Total-2	11,000						31,260	13.2					
M-3	2600	416	31	13	3	5	3848	1.9	38	- - -	- - -	- - -	9,543.00
M-3	2700	832	56	14	4	5	4509	2.2	41	(2) 40' - 42" L/ 45' R.C. Br.	- - -	15' R.C. Br.	
M-3	3900	1296	81	16	6	5	7956	3.6	46	- - -	- - -	- - -	
M-3	3900	1760	104	17	7	5	8658	3.8	49	- - -	- - -	- - -	
Total-3	13,100						24,971	11.5					
M-4	1900	3980	Old Kingstree Drainage District Canal, some renovation needed - detailed surveys required to determine design.	"	"	"	"	"	"	"	"	"	
M-4	2600	4104	"	"	"	"	"	"	"	"	"	"	
M-4	1800	4788	"	"	"	"	"	"	"	"	"	"	
M-4	5000	5480	"	"	"	"	"	"	"	"	"	"	
M-4	5000	6172	"	"	"	"	"	"	"	"	"	"	
M-4	5800	6660	"	"	"	"	"	"	"	"	"	"	
M-4	7000	11,110	"	"	"	"	"	"	"	"	"	"	
M-4	800	11,698	"	"	"	"	"	"	"	"	"	"	
M-4	4000	12,650	"	"	"	"	"	"	"	"	"	"	
M-4	4000	18,008	"	"	"	"	"	"	"	"	"	"	
M-4	2300	18,148	"	"	"	"	"	"	"	"	"	"	
M-4	4000	20,220	"	"	"	"	"	"	"	"	"	"	
M-4	3300	20,960	"	"	"	"	"	"	"	"	"	"	
L-1	1300	380	Old Kingstree Drainage District Canal, adequate as constructed, maintenance required.	"	"	"	"	"	"	"	"	"	
L-1	2800	464	"	"	"	"	"	"	"	"	"	"	
L-2	3700	530	"	"	"	"	"	"	"	"	"	"	
L-2	3600	690	"	"	"	"	"	"	"	"	"	"	
L-2	2800	810	"	"	"	"	"	"	"	"	"	"	
L-2	1900	846	"	"	"	"	"	"	"	"	"	"	
L-2	1500	3278	Old Kingstree Drainage District Canal, some renovation needed, detailed surveys required to determine design.	"	"	"	"	"	"	"	"	"	
L-2	3300	3490	"	"	"	"	"	"	"	"	"	"	
L-2	6600	3954	"	"	"	"	"	"	"	"	"	"	
L-3	6600	2032	"	"	"	"	"	"	"	"	"	"	
L-3	3300	2304	"	"	"	"	"	"	"	"	"	"	
L-3	2400	2380	"	"	"	"	"	"	"	"	"	"	





# ENGINEERING AND DESIGN DATA

## Area 7 - Kingstree - Cades - Moors

Sheet 2 of 3

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
L-4	5400	492	Old Kingstree	Drainage	District	Canal,	adequate as constructed,						
L-4	600	504	"	"	"	"	"	"	"	"	"	"	
L-5	1000	1206	"	"	"	"	"	"	"	"	"	"	
L-5	2800	1366	"	"	"	"	"	"	"	"	"	"	
L-5	5700	1950	"	"	"	"	"	"	"	"	"	"	
L-5	2200	2174	Old Kingstree	Drainage	District	Canal,	some renovation needed, detailed			surveys required to determine		design.	
L-5	6600	3346	"	"	"	"	"	"	"	"	"	"	
L-5	6700	4238	"	"	"	"	"	"	"	"	"	"	
L-5	7100	4742	"	"	"	"	"	"	"	"	"	"	
L-6	2000	584	42	13	3	5	2960	1.5	38	---	---	---	1,040.00
L-6	4600	1408	Old Kingstree	Drainage	District	Canal,	adequate as constructed, maintenance required.						
L-6	2700	1752	Old Kingstree	Drainage	District	Canal,	some renovation needed, detailed			surveys required to determine		design.	
L-6	1800	1824	"	"	"	"	"	"	"	"	"	"	
Total-4	136,500						2960	1.5					1,040.00
M-5	5100	948	Old Kingstree	Drainage	District	Canal,	adequate as constructed, maintenance required.						
M-5	4100	1464	"	"	"	"	"	"	"	"	"	"	
M-5	3100	1888	Old Kingstree	Drainage	District	Canal,	some renovation needed, detailed			surveys required to determine		design.	
M-5	5400	2300	"	"	"	"	"	"	"	"	"	"	
Total-5	17,700												
M-6	3800	592	Old Kingstree	Drainage	District	Canal,	adequate as constructed, maintenance required.						
M-6	6300	1000	"	"	"	"	"	"	"	"	"	"	
M-6	7600	1556	Old Kingstree	Drainage	District	Canal,	some renovation needed, detailed			survey required to determine		design.	
M-6	3500	1784	"	"	"	"	"	"	"	"	"	"	
Total-6	21,200												
M-7	4700	2636	Old Kingstree	Drainage	District	Canal,	some renovation needed, detailed			surveys required to determine		design.	
M-7	2000	3600	"	"	"	"	"	"	"	"	"	"	
M-7	3700	5324	"	"	"	"	"	"	"	"	"	"	
M-7	1600	5672	"	"	"	"	"	"	"	"	"	"	
M-7	600	5692	"	"	"	"	"	"	"	"	"	"	
M-7	2600	5756	"	"	"	"	"	"	"	"	"	"	
L-1	4600	468	34	13	3	5	6808	3.4	38	---	---	---	
L-1	3700	908	61	16	6	5	7548	3.4	46	(2)40' - 30" L	---	15' R.C. Br.	
L-1	4000	1144	73	16	6	5	8160	3.7	46	---	---	---	
Total-7	27,500						22,516	10.5					8,729.00
M-8	2300	148	13	13	3	5	3404	1.7	38	40' - 24" L	---	40' - 30"	
M-8	1700	192	16	13	3	5	2516	1.2	38	---	---	---	
M-8	2100	456	34	13	3	5	3108	1.5	38	---	---	---	



# ENGINEERING AND DESIGN DATA

Area 7 - Kingstree - Cades - Moores

Sheet 3 of 3

[illegible]

U. S. DEPARTMENT OF AGRICULTURE, SOIL CONSERVATION SERVICE  
USDA-SCS-FORT WORTH, TEX 1970

Work Sheet 3-70 4-R-29076-A





# ENGINEERING AND DESIGN DATA

Area 8 - Kingstree - Boggy Swamp

Sheet 1 of 3

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-1	4000	388	30	13	3	5	5920	2.9	38	30' - 30" L	- - -	30' - 42"	20,937.00
M-1	2900	548	40	13	3	5	4292	2.1	38	- - -	- - -	- - -	
M-1	1300	952	61	16	6	5	2652	1.2	46	(2)30' - 30" L	- - -	15' R.C. Br.	
M-1	2600	1032	68	16	6	5	5304	2.4	46	- - -	- - -	- - -	
M-1	4600	1744	103	19	9	5	11,914	5.2	55	(2) 8' x 8'	- - -	- - -	
M-1	1000	1768	105	19	9	5	2590	1.1	55	- - -	- - -	- - -	
L-1	4100	180	15	13	3	5	6068	3.0	38	40' - 18" L	- - -	40' - 30"	
L-1	2800	256	21	13	3	5	4144	2.1	38	40' - 36" L	- - -	- - -	
L-2	2000	196	17	13	3	5	2960	1.5	38	40' - 24"	40' - 36"	- - -	
L-2	4800	416	32	13	3	5	7104	3.5	38	- - -	- - -	- - -	
Total-1	30,100						52,948	25.0					
M-2	5900	492	36	13	3	5	8732	4.3	38	30' - 36" L	- - -	30' - 48"	16,115.00
M-2	2700	862	58	15	5	5	4995	2.4	44	- - -	- - -	- - -	
M-2	1000	2062	119	22	12	5	3150	1.3	62	(2)10' x 10'	- - -	- - -	
M-2	900	2122	123	22	12	5	2835	1.2	62	- - -	- - -	- - -	
L-1	4200	660	46	14	4	5	7014	3.4	41	None	- - -	15' R.C. Br.	
L-1	7400	1084	69	16	6	5	15,096	6.8	46	- - -	- - -	- - -	
Total-2	22,100						41,822	19.4					
M-3	1400	128	12	13	3	5	2072	1.0	38	(2)30' - 24" L	- - -	30' - 30"	
M-3	3000	260	21	13	3	5	4440	2.2	38	30' - 30" L	- - -	30' - 36"	
M-3	2500	428	32	13	3	5	3700	1.8	38	30' - 30" L	- - -	30' - 42"	
M-3	4000	736	51	14	4	5	6680	3.2	41	30' R.C. Br.	- - -	- - -	
M-3	900	780	53	15	5	5	1665	0.8	44	- - -	- - -	- - -	
Total-3	11,800						18,557	9.0					7,999.00
M-4	7500	428	32	13	3	5	11,100	5.5	38	15' R.C. Br.	- - -	- - -	5,935.00
M-4	4000	588	42	13	3	5	5920	2.9	38	- - -	- - -	- - -	
Total-4	11,500						17,020	8.4					
M-5	3400	180	15	13	3	5	5032	2.5	38	- - -	- - -	- - -	
M-5	6500	892	59	15	5	5	12,025	5.7	44	- - -	- - -	- - -	
M-5	500	1208	76	16	6	5	1020	0.5	46	7' x 7'	- - -	- - -	
M-5	2900	1340	84	17	7	5	6438	2.9	49	- - -	- - -	- - -	
M-5	1200	1180	75	16	6	5	2448	1.1	46	- - -	- - -	- - -	
M-5	2900	2012	116	22	12	5	9135	3.7	62	- - -	- - -	- - -	
L-1	2100	108	10	13	3	5	3108	1.5	38	40' - 24" L	40' - 24"	- - -	
L-1	2600	176	15	13	3	5	3848	1.9	38	40' - 24" L	- - -	- - -	

4-31983 7-72

- 47 -



# ENGINEERING AND DESIGN DATA

Area 8 - Kingstree - Boggy Swamp

Sheet 2 of 3

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
L-2	1800	88	9	13	3	5	2664	1.3	38	30' - 18" L	- -	30' - 24"	33,946.00
L-2	2100	220	18	13	3	5	3108	1.5	38	30' - 18" L	- -	30' - 36"	
L-2	1200	260	21	13	3	5	1776	0.9	38	- -	- -	- -	
L-3	2000	160	13	13	3	5	2960	1.5	38	40' - 24" L	- -	40' - 30"	
L-3	1500	184	16	13	3	5	2220	1.1	38	- -	- -	- -	
L-4	3300	176	15	13	3	5	4884	2.4	38	- -	- -	- -	
L-4	3200	704	48	14	4	5	5344	2.6	41	6' x 6'	- -	- -	
L-4	2400	880	59	15	5	5	4440	2.1	43	45' R.C. Br.	- -	- -	
L-4	500	904	60	16	6	5	1020	0.5	46	- -	- -	- -	
L-5	7400	492	36	13	3	5	10,952	5.4	38	40' - 36" L	- -	15' R.C. Br.	
L-5	1000	508	37	13	3	5	1480	0.7	38	- -	- -	- -	14,172.00
L-6	1300	104	10	13	3	5	1924	1.0	38	30' - 24"	- -	- -	
L-6	3000	216	18	13	3	5	4440	2.2	38	- -	- -	- -	
Total-5	51,800						90,266	43.0					
M-6	3000	684	48	14	4	5	5010	2.2	41	15' R.C. Br.	- -	- -	
M-6	3400	880	59	15	5	5	6290	3.0	44	30' - 36" L	- -	15' R.C. Br.	
M-6	5900	1936	113	20	10	5	16,402	6.9	57	(2) 40' - 36" L	- -	15' R.C. Br.	
M-6	2700	2104	122	22	12	5	8505	3.5	62	- -	- -	- -	
Total-6	15,000						36,207	15.6					
M-7	4000	448	33	13	3	5	5920	2.9	38	30' - 30" L	- -	30' - 42"	3,287.00
M-7	1100	480	35	13	3	5	1628	0.8	38	- -	- -	- -	
Total-7	5100						7548	3.7					
M-8	300	16	2	13	3	5	444	0.2	38	20' - 12" L	- -	30' - 24"	
M-8	3400	212	18	13	3	5	5032	2.5	38	(2) 3' x 8'	- -	- -	
M-8	4000	404	31	13	3	5	5920	2.9	38	- -	- -	- -	
Total-8	7700						11,396	5.6					
M-9	1800	204	16	13	3	5	2664	1.3	38	4' x 4'	- -	- -	
M-9	3200	436	33	13	3	5	4736	2.4	38	- -	- -	- -	
Total-9	5000						7400	3.7					
M-10	3900	308	24	13	3	5	5772	2.9	38	40' - 36"	40' - 36"	15' R.C. Br.	6,660.00
M-10	4100	564	40	13	3	5	6068	3.0	38	None	- -	- -	
M-10	2000	580	41	13	3	5	2960	1.5	38	- -	- -	- -	
Total-10	10,000						14,800	7.4					



# ENGINEERING AND DESIGN DATA

Area 8 - Kingstree - Boggy Swamp

Sheet 3 of 3

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c. f. s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-11	600	32	4	13	3	5	888	0.4	38	30' - 24"	30' - 24"	- - -	10,552.00
M-11	5600	264	21	13	3	5	8288	4.1	38	- - -	- - -	- - -	
M-11	1900	588	42	13	3	5	2812	1.4	38	40' - 48"	40' - 48"	- - -	
M-11	1100	624	44	14	4	5	1837	0.9	41	- - -	- - -	- - -	
M-11	1800	744	51	14	4	5	3006	1.4	41	- - -	- - -	- - -	
L-1	2900	92	9	13	3	5	4292	2.1	38	- - -	- - -	- - -	
L-2	2300	80	8	13	3	5	3404	1.7	38	- - -	- - -	- - -	
L-3	2000	56	6	13	3	5	2960	1.5	38	- - -	- - -	- - -	
Total-11	18,200						27,487	13.5					
M-12	1600	224	19	13	3	5	2368	1.2	38	(2) 30' - 15" L/	- - -	30' - 36"	1,993.00
M-12	1300	308	24	13	3	5	1924	1.0	38	- - -	- - -	- - -	
Total-12	2900						4292	2.2					
M-13	1500	60	6	13	3	5	2220	1.1	38	40' - 30"	40' - 30"	- - -	12,652.00
M-13	3300	212	18	13	3	5	4884	2.4	38	30' - 18" L/	- - -	30' - 30"	
M-13	1800	244	20	13	3	5	2664	1.3	38	- - -	- - -	- - -	
M-13	3100	1000	66	16	6	5	6324	2.8	46	- - -	- - -	- - -	
M-13	5900	1352	84	17	7	5	13,098	5.8	49	- - -	- - -	- - -	
L-1	3500	356	28	13	3	5	5180	2.6	38	- - -	- - -	- - -	
Total-13	19,100						34,370	16.0					
M-14	4500	628	44	14	4	5	7515	3.6	41	40' - 48" L/	40' - 48"	- - -	3,399.00
Total-14	4500						7515	3.6		40' - 48"			
L/ Remove or abandon (Not included in designed capacity.)													
NOTE: Figure in parenthesis in column 11 indicates number of culverts.													





# ENGINEERING AND DESIGN DATA

Area 9 - Salters - Lane - Gourdin

Sheet 1 of 4

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-1	4000	600	42	13	3	5	5920	2.9	38	- - -	- - -	- - -	5,778.00
M-1	1500	964	63	14	4	5	2505	1.2	41	5' x 5'	- - -	- - -	
M-1	800	1028	66	14	4	5	1336	.6	41	30' - 30" L	- - -	15' R.C. Br.	
M-1	2200	1112	71	15	5	5	4070	1.9	44	- - -	- - -	- - -	
Total-1	8500						13,831	6.6					
M-2	2700	264	21	13	3	5	3996	2.0	38	30' - 18" L	- - -	30' - 36"	18,876.00
M-2	1700	404	29	13	3	5	2516	1.2	38	40' - 48"	- - -	- - -	
M-2	4100	608	43	13	3	5	6068	3.0	38	- - -	- - -	- - -	
M-2	2200	1160	74	15	5	5	4070	1.9	44	8' x 8'	- - -	- - -	
M-2	1800	1244	78	16	6	5	3672	1.7	46	- - -	- - -	- - -	
M-2	4800	1846	108	17	7	5	10,656	4.7	49	- - -	- - -	- - -	
L-1	5000	252	20	13	3	5	7400	3.7	38	- - -	- - -	- - -	
L-2	3400	136	12	13	3	5	5032	2.5	38	40' - 36"	40' - 36"	- - -	
L-2	1400	182	15	13	3	5	2072	1.0	38	40' - 36"	40' - 36"	- - -	
L-2	1800	210	18	13	3	5	2664	1.3	38	- - -	- - -	- - -	
Total-2	28,900						48,146	23.0					
M-3	6300	620	44	13	3	5	9324	4.6	38	4' x 4'	- - -	- - -	19,200.00
M-3	1500	772	52	14	4	5	2504	1.2	41	- - -	- - -	- - -	
M-3	4900	1868	110	18	8	5	11,809	5.2	52	- - -	- - -	- - -	
L-1	2500	184	16	13	3	5	3700	1.8	38	40' - 30"	40' - 30"	- - -	
L-1	4800	412	31	13	3	5	7104	3.5	38	- - -	- - -	- - -	15' R.C. Br.
L-1	3400	756	52	14	4	5	5678	2.7	41	40' - 36" L	- - -	- - -	
L-1	2300	840	56	14	4	5	3841	1.9	41	- - -	- - -	- - -	
L-2	5000	172	15	13	3	5	7400	3.7	38	- - -	- - -	- - -	
Total-3	30,700						51,360	24.6					
M-4	3000	264	21	13	3	5	4440	2.2	38	40' - 36"	40' - 36"	- - -	7,145.00
M-4	3500	586	41	13	3	5	5180	2.6	38	- - -	- - -	- - -	
M-4	5700	908	60	14	4	5	9519	4.6	41	- - -	- - -	- - -	
Total-4	12,200						19,139	9.4					
M-5	5900	612	43	13	3	5	8732	4.3	38	- - -	- - -	- - -	22,923.00
M-5	5100	1120	72	16	6	5	10,404	4.7	46	40' - 42" L	- - -	15' R.C. Br.	
M-5	3000	1268	79	17	7	5	6660	3.0	49	- - -	- - -	- - -	
M-5	600	2244	128	19	9	5	1554	0.7	55	20' U.T.Br. L	- - -	15' R.C. Br.	
M-5	4500	2468	139	20	10	5	12,510	5.3	57	- - -	- - -	- - -	
L-1	4700	472	35	13	3	5	6956	3.5	38	- - -	- - -	- - -	
L-1	4000	788	52	14	4	5	6680	3.2	41	40' - 42" L	- - -	15' R.C. Br.	
L-1	2800	908	60	14	4	5	4676	2.2	41	- - -	- - -	- - -	
Total-5	30,600						58,172	26.9					



# ENGINEERING AND DESIGN DATA

Area 9 - Salters-Lane-Gourdin

Sheet 2 of 4

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-6 M-6 Total-6	3700 7500 11,200	428 756	32 52	13 14	3 4	5 5	5476 12,525 18,001	2.7 6.0 8.7	38 41	(2)20'-18" L/ - - -	- - - - - -	30' - 42" - - -	6,900.00
M-7 M-7 Total-7	5000 3300 8300	516 672	38 47	13 14	3 4	5 5	7400 5511 12,911	3.7 2.7 6.4	38 41	(2)30'-18" L/ - - -	- - - - - -	30' - 48" - - -	5,288.00
M-8 M-8 Total-8	4600 4600	144	13	13	3	5	6808 6808	3.4 3.4	38	- - -	- - -	- - -	2,382.00
M-9 M-9 Total-9	4000 4000	216	18	13	3	5	5920 5920	2.9 2.9	38	- - -	- - -	- - -	2,060.00
M-10 M-10 Total-10	4000 6700 10,700	404 612	31 43	13 13	3 3	5 5	5920 9916 15,836	2.9 4.9 7.8	38 38	4' x 4' - - -	- - - - - -	- - -	5,519.00
M-11 M-11 M-11 M-11 M-11 M-11 L-1 L-1 L-2 Total-11	2100 1800 1500 1500 5000 7100 4000 4300 29,800	2688 3144 3232 3332 4856 6952 7780 624 888 1168	33 2/ 67 3/ 72 3/ 78 3/ 158 3/ 218 3/ 253 3/ 44 59 17 2/	Adequate as constructed 15 15 16 22 26 30 14 15 Adequate as constructed	5 5 6 12 16 20 4 5 5	5 5 5 5 5 5 5 5 5	- requires 3885 3330 3060 12,600 19,450 32,873 6680 7955 89,833	requires 1.8 1.6 1.4 5.1 7.7 12.7 3.2 3.8 37.3	44 44 46 62 73 84 41 44	30' R.C. Br. 20' U.T. Br. -	- -	15' R.C. Br. -	31,219.00
M-12 M-12 M-12 M-12 Total-12	7700 2000 300 1300 12,300	600 820 920 1040 1112	42 55 60 67 71	13 13 14 15 15	3 3 4 5 5	5 5 5 5 5	11,396 2960 501 2405 1850 19,112	5.7 1.5 0.2 1.1 0.9 9.4	38 38 41 44 44	- - - None 40' - 24" L/ (2)40' - 30" L/ - - -	- - - - - - - - - - - - - - -	15' R.C. Br. 15' R.C. Br. 15' R.C. Br. - - - - - -	9,658.00
M-13 M-13	1900 4500	180 416	10 32	13 13	3 3	5 5	2812 6660	1.4 3.3	38 38	40' - 24" L/ - - -	- - - - - -	40' - 30" - - -	



# ENGINEERING AND DESIGN DATA

Area 9 - Salters-Lane-Gourdin

Sheet 3 of 4

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-13 L-1 L-1 Total-13	1800 4000 12,200	1472 712 1304	90 81	16 Adequate as constructed 16	6 6	5 5	3672 8160 21,304	1.7 3.7 10.1	46 46	- - - - - -	- - - - - -	- - - - - -	7,786.00
M-14 M-14 Total-14	3500 6900 10,400	372 760	28 52	13 14	3 4	5 5	5180 11,523 16,703	2.6 5.5 8.1	38 41	None - - -	- - - - - -	30' - 32" - - -	6,456.00
M-15 M-15 M-15 M-15 L-1 L-1 L-1 L-1 L-1 L-1 L-1 L-1 L-2 L-2 L-2 L-3 L-4 Total-15	4100 7600 6500 7100 3700 500 2300 1700 1700 5600 4700 2800 48,300	88 2332 3352 3704 572 780 1344 1448 1916 208 524 412 156	131 178 194 41 54 84 88 112 18 38 31 14	Adequate as constructed 22 24 24 13 15 17 18 20 13 13 13 13	12 14 14 3 5 7 8 10 3 3 3 3	5 5 5 5 5 5 5 5 5 5 5 5	- requires maintenance. 12,915 26,752 22,880 10,508 6845 1110 5545 4726 2516 8288 6956 4144 113,185	5.3 10.8 9.3 5.2 3.2 0.5 2.4 2.0 1.2 4.1 3.5 2.1 49.6	62 68 68 38 44 49 52 57 38 38 38 38	- -			





# ENGINEERING AND DESIGN DATA

Area 9 - Salters-Lane-Gourdin

Sheet 4 of 4

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
L-1	4400	384	29	13	3	5	6512	3.2	38	- - -	- - -	- - -	
L-2	1800	272	22	13	3	5	2664	1.3	38	None	- - -	30' - 36"	
L-2	55	760	52	14	4	5	9185	4.4	41	- - -	- - -	- - -	
Total-18	39,400						86,727	38.4					33,842.00
<p>1/ Remove or abandon (Not included in designed capacity.)</p> <p>2/ Runoff curve used: <math>Q = 10 M^{5/6}</math>.</p> <p>3/ Runoff curve used: <math>Q = 45 M^{5/6}</math> for accumulated area applicable + Q curve for segment (s) using other runoff coefficients.</p> <p>NOTE: Figure in parenthesis in column 11 indicates number of culverts.</p>													

4-31983 7-72



# ENGINEERING AND DESIGN DATA

Area 10 - Hebron - Mouzon - Bennett Swamp

Sheet 1 of 3

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-1	10,200	728	11 2/	13	3	5	15,096	7.4	38	- - -	- - -	- - -	13,591.00
M-1	3200	1032	35 3/	13	3	5	4736	2.4	38	- - -	- - -	- - -	
M-1	2400	2160	65 3/	16	6	5	4896	2.2	46	- - -	- - -	- - -	
L-1	7400	844	13 2/	13	3	5	10,952	5.4	38	- - -	- - -	- - -	
L-1	2300	952	23 3/	13	3	5	3404	1.7	38	- - -	- - -	- - -	
Total-1	25,500						39,084	19.1					
M-2	6700	972	64	16	6	5	13,668	6.2	46	- - -	- - -	- - -	14,027.00
M-2	5400	1300	81	17	7	5	11,988	5.3	49	40' - 36" L/	- - -	15' R.C. Br.	
M-2	5300	2016	117	18	8	5	12,773	5.6	52	40' - 24" L/	- - -	- - -	
Total-2	17,400						38,429	17.1		- - -	- - -	- - -	
M-3	5000	808	13 2/	13	3	5	7400	3.7	38	- - -	- - -	- - -	
M-3	5300	1424	56 3/	14	4	5	8851	4.3	41	(2) 40' - 30" L/	- - -	15' R.C. Br.	10,034.00
M-3	5300	1676	71 3/	15	5	5	9805	4.6	44	- - -	- - -	- - -	
Total-3	15,600						26,056	12.6		- - -	- - -	- - -	
M-4	7000	544	39	13	3	5	10,360	5.1	38	40' - 30" L/	- - -	15' R.C. Br.	
Total-4	9700	616	43	13	3	5	14,356	7.1	38	- - -	- - -	- - -	
M-5	5300	840	13 2/	13	3	5	7844	3.9	38	- - -	- - -	- - -	14,637.00
M-5	4100	1136	16 2/	13	3	5	6068	3.0	38	40' - 24" L/	- - -	15' R.C. Br.	
M-5	3300	1280	29 3/	13	3	5	4834	2.4	38	- - -	- - -	- - -	
M-5	2200	2000	74 3/	15	5	5	4070	1.9	44	- - -	- - -	- - -	
L-1	5300	368	28	13	3	5	7844	3.9	38	40' - 24" L/	- - -	40' - 42"	
Total-5	24,200	600	42	13	3	5	5920	2.9	38	- - -	- - -	- - -	
							36,630	18.0					14,637.00
M-6	6000	296	23	13	3	5	8880	4.4	38	40' - 36"	40' - 36"	- - -	5,431.00
M-6	1800	368	28	13	3	5	2664	1.3	38	30' - 30" L/	- - -	30' - 42"	
M-6	500	380	29	13	3	5	740	0.4	38	- - -	- - -	- - -	
Total-6	8300						12,284	6.1					
M-7	4100	216	18	13	3	5	6068	3.0	38	(2) 30' - 24"	(2) 30' - 24"	- - -	
M-7	1900	292	23	13	3	5	2812	1.4	38	40' - 42"	40' - 42"	- - -	
M-7	1400	312	24	13	3	5	2072	1.0	38	- - -	- - -	- - -	
Total-7	7400						10,952	5.4					4,858.00

4-31983 7-72

1 54 1



# ENGINEERING AND DESIGN DATA

Area 10 - Hebron - Mouzon - Bennett Swamp

Sheet 2 of 3

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-8	3800	468	34	13	3	5	5624	2.8	38	- - -	- - -	- - -	8,142.00
M-8	3500	976	64	16	6	5	7140	3.2	46	- - -	- - -	- - -	
M-8	4600	1516	92	18	8	5	11,086	4.9	52	- - -	- - -	- - -	
Total-8	11,300						23,850	10.9					
M-9	9600	1272	Old County Line Canal - Adequate as constructed - maintenance required.									15' R.C. Br.	14,232.00
M-9	2900	2278	28 2/3	13	3	5	4292	2.1	38	20' - 15" L/	- - -	- - -	
M-9	3100	2532	32 2/3	13	3	5	4588	2.3	38	- - -	- - -	- - -	
M-9	3300	2648	43 3/4	13	3	5	4884	2.4	38	- - -	- - -	- - -	
M-9	2100	3824	93 3/4	18	8	5	5061	2.2	52	- - -	- - -	- - -	
L-1	6900	756	Old County Line Canal - Adequate as constructed - maintenance required.									30' - 42"	
L-2	2400	368	6 2/3	13	3	5	3553	1.8	38	(2)30' - 15" L/	- - -	15' R.C. Br.	
L-2	4500	848	13 2/3	13	3	5	6660	3.3	38	20' - 18" L/	- - -	- - -	
L-2	1000	928	14 2/3	13	3	5	1480	0.7	38	- - -	- - -	- - -	
L-2	1900	1088	28 3/4	13	3	5	2812	1.4	38	- - -	- - -	- - -	
Total-9	37,700						33,330	16.2					
M-10	5300	452	33	13	3	5	7844	3.9	38	(2)40' - 24" L/	- - -	40' - 42"	4,963.00
M-10	2600	540	39	13	3	5	3848	1.9	38	- - -	- - -	- - -	
Total-10	7900						11,692	5.8					
M-11	4000	284	22	13	3	5	5920	2.9	38	40' - 36"	40' - 36"	- - -	3,164.00
M-11	1200	296	23	13	3	5	1776	0.9	38	- - -	- - -	- - -	
Total-11	5200						7696	3.8					
M-12	7900	728	50	14	4	5	13,193	6.3	41	15' R.C. Br.	- - -	- - -	19,779.00
M-12	3300	1008	66	16	6	5	6732	3.0	46	- - -	- - -	- - -	
M-12	5300	1596	97	19	9	5	13,727	6.0	55	45' R.C.Br.	- - -	- - -	
M-12	1500	1664	104	19	9	5	3885	1.7	55	- - -	- - -	- - -	
L-1	4500	256	21	13	3	5	6660	3.3	38	40' - 30" L/	- - -	40' - 36"	
L-1	2900	484	36	13	3	5	4292	2.1	38	- - -	- - -	- - -	
L-1	4400	764	52	14	4	5	7348	3.5	41	- - -	- - -	- - -	
Total-12	29,800						55,837	25.9					
M-13	2500	250	20	13	3	5	3700	1.8	38	30' - 18" L/	- - -	30' - 36"	15' R.C. Br.
M-13	3000	590	41	13	3	5	4440	2.2	38	- - -	- - -	- - -	
M-13	2900	930	62	16	6	5	5916	2.7	46	30' - 30" L/	- - -	- - -	
M-13	4300	1342	84	17	7	5	9546	4.2	49	30' - 24" L/	- - -	- - -	
M-13	4400	1754	104	19	9	5	10,604	4.9	55	(3)10' x 10'	- - -	- - -	

4-31913 7-72

55





# ENGINEERING AND DESIGN DATA

Area 10 - Hebron - Mourzon - Bennett Swamp

Sheet 3 of 3

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-13 Total-13	2200 19,300	1886	111	20	10	5	6116 40,322	2.6 18.4	57	- - -	- - -	- - -	15,200.00
M-14	4400	308	24	13	3	5	6512	3.2	38	40' - 18"L/ 40' - 30"L/ 7' x 6'	- - - - - - - - -	40' - 36" - - - - - -	30,259.00
M-14	3000	792	54	15	5	5	5550	2.6	44	- - -	- - -	- - -	
M-14	1200	828	55	15	5	5	2220	1.0	44	- - -	- - -	- - -	
M-14	3800	3040	166	22	12	5	11,970	4.9	62	- - -	- - -	- - -	
L-1	1600	216	18	13	3	5	2368	1.2	38	20' - 18"L/ 40' - 24"L/ 30' - 30"L/ 30' - 30"L/ 30' - 30"L/ (2)40' - 36"L/ - - -	- -	30' - 36" 15' R.C. Br. 15' R.C. Br. 15' R.C. Br. 15' R.C. Br. 15' R.C. Br. 15' R.C. Br.	
L-1	4800	656	45	14	4	5	8016	3.9	41	- - -	- - -	- - -	
L-1	2600	804	55	15	5	5	4810	2.3	44	- - -	- - -	- - -	
L-1	1000	944	62	16	6	5	2040	0.9	46	- - -	- - -	- - -	
L-1	600	984	65	16	6	5	1224	0.6	46	- - -	- - -	- - -	
L-1	800	1016	66	16	6	5	1632	0.7	46	- - -	- - -	- - -	
L-1	3000	1290	80	17	7	5	6660	3.0	49	- - -	- - -	- - -	
L-1	2300	1564	95	18	8	5	5543	2.4	52	- - -	- - -	- - -	
L-1 Total-14	32,500	1820	108	20	10	5	9452 67,997	4.0 30.7	57	- - - - - - - - -	- - - - - - - - -	- - - - - - - - -	
M-15 Total-15	4600 4100 8700	268 504	22 37	13 13	3 3	5 5	6808 6068 12,876	3.4 3.0 6.4	38 38	20' - 15"L/ - - -	- - - - - - - - -	30' - 36" - - - - - -	4,979.00
1/ Remove or abandon (Not included in designed capacity.)													
2/ Runoff curve used: $Q = 10M^{5/6}$ .													
3/ Runoff curve used: $Q = 45M^{5/6}$ for accumulated area applicable + Q curve for segment(s) using other runoff coefficients.													
NOTE: Figure in parenthesis in column 11 indicates number of culverts.													



# ENGINEERING AND DESIGN DATA

Area 11 - Greeleyville - Heineman

Sheet 1 of 3

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-1	6800	624	10 2/	13	3	5	10,064	5.0	38	- - -	- - -	- - -	
M-1	1900	1528	21 2/	13	3	5	2812	1.4	38	- - -	- - -	- - -	
M-1	3000	2040	57 3/	15	5	5	5550	2.6	44	- - -	- - -	- - -	
M-1	1500	3104	116 3/	22	12	5	4725	1.9	62	45' R.C. Br.	- - -	- - -	
M-1	3900	3664	143 3/	24	14	5	13,728	5.6	68	- - -	- - -	- - -	
M-1	2600	4192	168 3/	26	16	5	10,114	4.0	73	(2)40' - 60" L	- - -	30' R.C. Br.	
M-1	4800	4848	197 3/	30	20	5	22,224	8.6	84	- - -	- - -	- - -	
M-1	1000	5256	217 3/	32	22	5	5000	1.9	89	- - -	- - -	- - -	
L-1	1500	248	10 2/	13	3	5	2220	1.1	38	20' - 15"	- - -	30' - 36"	
L-1	3500	392	7 2/	13	3	5	5180	2.6	38	- - -	- - -	- - -	
L-2	3800	188	16	13	3	5	5624	2.8	38	(2)20' - 15" L	- - -	30' - 36"	
L-2	3600	384	29	13	3	5	5328	2.6	38	- - -	- - -	- - -	
L-3	5700	600	43	13	3	5	8436	4.2	38	- - -	- - -	- - -	
L-3	4000	776	53	15	5	5	7400	3.5	44	- - -	- - -	- - -	
L-4	5900	352	27	13	3	5	8732	4.3	38	- - -	- - -	- - -	
Total-1	53,500						117,137	52.1					42,664.00
M-2	4200	300	24	13	3	5	6216	3.1	38	4' x 4'	- - -	- - -	
M-2	1200	320	25	13	3	5	1776	0.9	38	- - -	- - -	- - -	
Total-2	5400						7992	4.0					2,798.00
M-3	3800	1076	43 2/	13	3	5	5624	2.8	38	(4)30' - 30" L	- - -	15' R.C. Br.	
M-3	700	1160	48 2/	14	4	5	1169	0.6	41	- - -	- - -	- - -	
M-3	2500	2552	87 3/	18	8	5	6025	2.6	52	30' U.T. Br.	- - -	- - -	
M-3	3400	3092		Canal adequate as constructed - maintenance required.									
L-1	6300	588		"	"	"	"	"	"	"			
L-1	300	648		"	"	"	"	"	"	"			
L-1	5000	964		"	"	"	"	"	"	"			
L-1	1200	1115		"	"	"	"	"	"	"			
L-1	500	1120		"	"	"	"	"	"	"			
L-2	2400	96	9	13	3	5	740	0.4	38	- - -	- - -	- - -	
Total-3	21,600						16,370	7.8					6,652.00
M-4	3500	620	43	13	3	5	5180	2.6	38	- - -	- - -	- - -	
M-4	3300	848	57	15	5	5	6105	2.9	44	- - -	- - -	- - -	
M-4	3200	1080	69	16	6	5	6528	2.9	46	- - -	- - -	- - -	
M-4	3200	1328	83	17	7	5	7104	3.2	49	None	- - -	15' R.C. Br.	
M-4	4000	1572	96	19	9	5	10,360	4.5	55	- - -	- - -	- - -	
M-4	1300	1856	110	20	10	5	3614	1.5	57	- - -	- - -	- - -	
M-4	1700	2412	136	20	10	5	5984	2.4	68	40' - 24" L	- - -	30' R.C. Br.	
M-4	800	2436	137	24	14	5	2816	1.1	68	- - -	- - -	- - -	
M-4	400	2656	147	24	14	5	1408	0.6	68	30' - 36" L	- - -	30' R.C. Br.	



# ENGINEERING AND DESIGN DATA

Arca 11 - Greeleyville - Heineman

Sheet 2 of 3

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-4 L-1 L-2 L-3 Total-4	6300 4400 5100 500 3200 40,900	3344 236 376 48 208	177 20 30 5 17	28 13 13 13 13	18 3 3 3 3	5 5 5 5 5	26,838 6512 7548 740 4736 95,473	10.4 3.2 3.7 0.4 2.4 41.8	78 38 38 38 38	- - - - - - 30' - 18" L/ 40' - 24" L/ - - -	- - - - - - 40' - 24" L/ - - -	- - - - - - 30' - 42" L/ - - -	38,128.00
M-5 M-5 M-5 L-1 L-1 L-2 Total-5	5200 6600 500 4500 3000 6700 26,500	656 1736 2076 440 656 324	10 2/ 79 2/ 99 2/ 33 46 25	13 17 19 13 14 13	3 7 9 3 4 3	5 5 5 5 5 5	7696 14,652 1295 6660 5010 9916 45,229	3.8 6.5 0.6 3.3 2.4 4.9 21.5	38 49 55 38 41 38	- - - - - - 45' R.C. Br. - - - - - - - - -	- - - - - - - - - - - - - - - - - -	- - - - - - - - - - - - - - - - - -	15,607.00
M-6 M-6 M-6 L-1 Total-6	1500 2000 4800 1500 4500 14,300	180 260 748 788 176	15 21 51 54 15	13 13 14 15 13	3 3 4 5 3	5 5 5 5 5	2220 2960 8016 2775 6660 22,631	1.1 1.5 3.9 1.3 3.3 11.1	38 38 41 44 38	None - - - 30' - 24" L/ - - - - - -	- - - - - - - - - - - - - - -	40' - 36" L/ 15' R.C. Br. - - - - - -	9,518.00
M-7 M-7 M-7 Total-7	1500 200 2200 2600	108 132 224 304		Canal " " " "	adequate " " " "	as constructed - maintenance required. " " " "							
M-8 M-8 M-8 M-8 L-1 L-1 Total-8	2000 3000 1400 2500 1800 2500 13,200	140 412 652 748 76 156	13 57 2/ 72 3/ 78 2/ 19 4/ 36 4/	13 15 16 17 13 13	3 5 6 7 3 3	5 5 5 5 5 5	2960 5550 2856 5550 2664 3700 23,280	1.5 2.6 1.3 2.5 1.3 2.7 11.9	38 42 46 49 38 38	- - - - - - 30' - 15" L/ 4' x 4' - - - None - - -	- - - - - - - - - - - - - - - - - -	30' - 42" L/ - - - - - - 30' - 24" L/ - - -	9,099.00
M-9 M-9 M-9 M-9	5800 3400 3000 1000	532 1376 2088 2172	38 86 121 125	13 18 22 22	3 8 12 12	5 5 5 5	8584 8194 9450 3150	4.3 3.6 3.9 1.3	38 52 62 62	- - - - - - (2)30' - 36" L/ (5)40' - 48" L/	- - - - - - - - - - - -	- - - - - - 30' R.C. Br. - - -	

4-31983 7-72

1 50 1





# ENGINEERING AND DESIGN DATA

Arca 11 - Greeleyville - Heineman

Sheet 3 of 3

CANAL No. (1)	LENGTH Ft. (2)	WATERSHED Ac. (3)	DISCHARGE c.f.s. (4)	CHANNEL DIMENSIONS			EXCAVATION Cu. Yds. (8)	RT. OF WAY CLEARING Ac. (9)	REQUIRED RT. OF WAY WIDTH Ft. (10)	CULVERTS EXISTING Length & Size (11)	CULVERTS LOWERING Length & Size (12)	CULVERTS & BRIDGES-NEW Length & Size (13)	TOTAL ESTIMATED COST DOLLARS (14)
				TOP WIDTH Ft. (5)	BOTTOM WIDTH Ft. (6)	AVERAGE DEPTH Ft. (7)							
M-9	1100	2232	127	22	12	5	3465	1.4	62	(2) 30' - 30" L/ 30' - 36" L	- - -	- - -	49,935.00
M-9	900	2984	163	26	16	5	3501	1.4	73	- - -	- - -	30' R.C. Br.	
M-9	2000	3048	167	26	16	5	7780	3.1	73	- - -	- - -	- - -	
M-9	1400	5092	255	34	24	5	7518	2.8	94	(2) 8' x 8'	- - -	- - -	
L-1	3200	280	23	13	3	5	4736	2.4	38	30' - 24" L	- - -	30' - 36"	
L-1	2900	460	34	13	3	5	4292	2.1	38	- - -	- - -	- - -	
L-2	1300	80	7	13	3	5	1924	1.0	38	30' - 18" L	- - -	30' - 24"	
L-2	2900	180	15	13	3	5	4292	2.1	38	- - -	- - -	- - -	
L-3	3000	208	17	13	3	5	4440	2.2	38	4' x 4'	- - -	- - -	
L-3	5100	528	38	13	3	5	7548	3.7	38	40' - 60"	- - -	- - -	
L-4	5300	540	39	13	3	5	7844	3.9	38	- - -	- - -	- - -	
L-4	1100	604	43	13	3	5	1628	0.8	38	- - -	- - -	- - -	
L-5	6100	544	39	13	3	5	9028	4.5	38	None	- - -	30' - 48"	
L-5	1600	636	43	13	3	5	2368	1.2	38	(2) 30' - 18" L	- - -	15' R.C. Br.	
L-5	2100	660	46	14	4	5	3507	1.7	41	- - -	- - -	- - -	
L-6	3400	808	55	15	5	5	6290	3.0	44	40' - 18" L	- - -	15' R.C. Br.	
L-6	1000	844	57	15	5	5	1850	0.9	44	None	- - -	15' R.C. Br.	
L-6	4800	976	64	16	6	5	9792	4.4	46	- - -	- - -	- - -	
Total-9	62,400						121,181	55.7					
M-10	7500	540	39	13	3	5	11,100	5.5	38	30' - 18" L	- - -	30' - 48"	6,810.00
M-10	2000	676	47	14	4	5	3340	1.6	41	40' - 36" L	- - -	15' R.C. Br.	
Total-10	9500						14,440	7.1					
M-11	4000	416	31	13	3	5	5920	2.9	38	6' x 8'	- - -	- - -	2,060.00
Total-11	4000						5920	2.9					
<p>1/ Remove or abandon (Not included in designed capacity.)</p> <p>2/ Runoff curve used: <math>Q = 10 M^{5/6}</math>.</p> <p>3/ Runoff curve used: <math>Q = 45 M^{5/6}</math> for accumulated area applicable + Q curve for segment(s) using other runoff coefficients.</p> <p>4/ Runoff curve used: <math>Q = 118 M^{5/6}</math>.</p> <p>NOTE: Figure in parenthesis in column 11 indicates number of culverts.</p>													



CC

52

41

45

8

8

2

M-1

L-1





Figure No. 3

FEASIBILITY STUDY OF REQUIREMENTS FOR MAIN DRAINAGE CANALS  
WILLIAMSBURG COUNTY, SOUTH CAROLINA



INDEX TO MAP SHEETS

# AGE CANALS IN WILLIAMSBURG COUNTY, SOUTH CAROLINA

---

## ONVENTIONAL SIGNS


- Primary Road System
  - Federal Highway
  - State Highway
  - County Road
  - School
  - Church
- County Line
- Planning Unit Boundary and Number
- Watershed Boundary
- Main
- Lateral
- Indicates existing canals or natural drainage in swamp















# FEASIBILITY STUDY OF REQUIREMENTS FOR MAIN DRAINAGE

(Joins sheet 1)

2




CONVENTIONAL SIGNS

	Primary Road System
	Federal Highway
	State Highway
	County Road
	School
	Church
	County Line
	Planning Unit Boundary and Number
	Watershed Boundary
	Main
	Lateral
	Indicates existing canals or natural drainage in swamp




This is one set of maps prepared by the Soil Conservation Service, U.S. Department of Agriculture, for a feasibility study of requirements for main ditch drainage canals in Williamsburg County, South Carolina. The maps have been prepared in cooperation with Williamsburg County Soil and Water Conservation District and under the financial sponsorship of Williamsburg County. For information regarding the complete feasibility study report, write the Soil Conservation Service, U.S. Department of Agriculture, Columbia, South Carolina. This map was compiled as an uncontrolled mosaic from aerial photographs flown in 1966. Maps were prepared and surveys executed in 1972.





# SE CANALS IN WILLIAMSBURG COUNTY, SOUTH CAROLINA



(Joins sheet 3)


(Joins sheet 6)

5000 Feet





(Joins sheet 3)



(Joins sheet 8)

0 1/2 1 Mile  
Scale 1:50,000  
(Approximate)

2

(Joins sheet 1)

Scale 150 000  
1:500,000

(Joins sheet 6)



This is one set of maps prepared by the Soil Conservation Service, U.S. Department of Agriculture, for a feasibility study of requirements for main ditch drainage canals in Williamsburg County, South Carolina. The maps have been prepared in cooperation with Williamsburg County Soil and Water Conservation District and under the financial sponsorship of Williamsburg County. For information regarding the complete feasibility study report, write the Soil Conservation Service, U.S. Department of Agriculture, Columbia, South Carolina. This map was compiled as an uncontrolled mosaic from aerial photographs flown in 1966. Maps were prepared and surveys executed in 1972.



(Joins sheet 2)


(Joins sheet 4)

(Joins sheet 7)

0 1/2 1 Mile Scale 1:50,000 (Approximate) 0 5000 Feet




# GE CANALS IN WILLIAMSBURG COUNTY, SOUTH CAROLINA






(Joins sheet 5)







(Joins sheet 3)

(Joins sheet 8)

0 1/2 1 Mile Scale 1:50,000 (Approximate) 0 5000 Feet

# FEASIBILITY STUDY OF REQUIREMENTS FOR MAIN DRAINAGE CANALS IN WILLIAMSBURG COUNTY, SOUTH CAROLINA

(Joins inset sheet 5)


5

This is one set of maps prepared by the Soil Conservation Service, U.S. Department of Agriculture, for a feasibility study of requirements for main ditch drainage canals in Williamsburg County, South Carolina. The maps have been prepared in cooperation with Williamsburg County Soil and Water Conservation District and under the financial sponsorship of Williamsburg County. For information regarding the complete feasibility study report, write the Soil Conservation Service, U.S. Department of Agriculture, Columbia, South Carolina. This map was compiled as an uncontrolled mosaic from aerial photographs flown in 1966. Maps were prepared and surveys executed in 1972.




(Joins sheet 5)

(Joins sheet 2)



(Joins sheet 9)


(Joins sheet 6)





# IRIGATION CANALS IN WILLIAMSBURG COUNTY, SOUTH CAROLINA

(Sheet 2)



(Joins sheet 7)


(Joins sheet 10)



# FEASIBILITY STUDY OF REQUIREMENTS FOR MAIN DRAINAGE

(Joins sheet 4)

8



(Joins sheet 7)

(Joins inset, sheet 8)

0 1/2 1 Mile Scale 1:50 000 (Approximate)



FEASIBILITY STUDY OF REQUIREMENTS FOR MAIN DRAINAGE CANALS IN WILLIAMSBURG COUNTY, SOUTH CAROLINA

(Joins sheet 2)

6

N

(Joins sheet 5)



(Joins sheet 7)

# FEASIBILITY STUDY OF REQUIREMENTS FOR MAIN DRAINAGE CANALS IN WILLIAMSBURG COUNTY, SOUTH CAROLINA

7

This is one set of maps prepared by the Soil Conservation Service, U.S. Department of Agriculture, for a feasibility study of requirements for main ditch drainage canals in Williamsburg County, South Carolina. The maps have been prepared in cooperation with Williamsburg County Soil and Water Conservation District and under the financial sponsorship of Williamsburg County. For information regarding the complete feasibility study report, write the Soil Conservation Service, U.S. Department of Agriculture, Columbia, South Carolina. This map was compiled as an uncontrolled mosaic from aerial photographs flown in 1966, maps were prepared and surveys executed in 1972.



(Joins sheet 6)

(Joins sheet 8)

(Joins sheet 11)


Scale 1:50,000 (Approximate)



# GE CANALS IN WILLIAMSBURG COUNTY, SOUTH CAROLINA



10



(Joins sheet 9)


(Joins sheet 12)



# FEASIBILITY STUDY OF REQUIREMENTS FOR MAIN DRAINAGE CANALS IN WILLIAMSBURG COUNTY, SOUTH CAROLINA

8

(Joins sheet 4)



(Joins inset, sheet 8)

0 1/2 1 Mile Scale 1:50,000 (Approximate) 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80 81 82 83 84 85 86 87 88 89 90 91 92 93 94 95 96 97 98 99 100 Feet

(Joins sheet 8)






# FEASIBILITY STUDY OF REQUIREMENTS FOR MAIN DRAINAGE CANALS IN WILLIAMSBURG COUNTY, SOUTH CAROLINA

(Joins sheet 5)

This is one set of maps prepared by the Soil Conservation Service, U.S. Department of Agriculture, for a feasibility study of requirements for main ditch drainage canals in Williamsburg County, South Carolina. The maps have been prepared in cooperation with Williamsburg County Soil and Water Conservation District and under the financial sponsorship of Williamsburg County. For information regarding the complete feasibility study report, write the Soil Conservation Service, U.S. Department of Agriculture, Columbia, South Carolina. This map was compiled as an uncontrolled mosaic from aerial photographs flown in 1966. Maps were prepared and surveys executed in 1972.



0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80 81 82 83 84 85 86 87 88 89 90 91 92 93 94 95 96 97 98 99 100


Scale 1:50,000 (Approximate)

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80 81 82 83 84 85 86 87 88 89 90 91 92 93 94 95 96 97 98 99 100

(Joins sheet 10)

N

9



(Joins sheet 11)

(Joins sheet 13)



# FEASIBILITY STUDY OF REQUIREMENTS FOR MAIN DRAINAGE

12

(Joins sheet 9)

(Joins sheet 13)



FEASIBILITY STUDY OF REQUIREMENTS FOR MAIN DRAINAGE CANALS IN WILLIAMSBURG COUNTY, SOUTH CAROLINA

(Joins sheet 6)


10



(Joins sheet 9)

(Joins sheet 11)

(Joins sheet 12)



(Joins sheet 13)



# FEASIBILITY STUDY OF REQUIREMENTS FOR MAIN DRAINAGE CANALS IN WILLIAMSBURG COUNTY, SOUTH CAROLINA

(Joins sheet 7)

11



0 1/2 1 Mile Scale 1:50,000 (Approximate) 0 5000 Feet (Joins sheet 13)

This is one set of maps prepared by the Soil Conservation Service, U.S. Department of Agriculture, for a feasibility study of requirements for main ditch drainage canals in Williamsburg County, South Carolina. The maps have been prepared in cooperation with Williamsburg County Soil and Water Conservation District and under the financial sponsorship of Williamsburg County. For information regarding the complete feasibility study report, write the Soil Conservation Service, U.S. Department of Agriculture, Columbia, South Carolina. This map was compiled as an uncontrolled mosaic from aerial photographs flown in 1966. Maps were prepared and surveys executed in 1972.

(Joins sheet 10)

(Joins inset, sheet 8)



GE CANALS IN WILLIAMSBURG COUNTY, SOUTH CAROLINA  
(10)



(Joins sheet 13)

(Joins sheet 14)

# FEASIBILITY STUDY OF REQUIREMENTS FOR MAIN DRAINAG

14

(Joins sheet 12)

(Joins sheet 45)




FEASIBILITY STUDY OF REQUIREMENTS FOR MAIN DRAINAGE CANALS IN WILLIAMSBURG COUNTY, SOUTH CAROLINA


12

(Joins sheet 9)

(Joins sheet 10)



(Joins sheet 13)



(Joins sheet 14)



# FEASIBILITY STUDY OF REQUIREMENTS FOR MAIN DRAINAGE CANALS IN WILLIAMSBURG COUNTY, SOUTH CAROLINA

(Joins sheet 10)

(Joins sheet 11)

13

This is one set of maps prepared by the Soil Conservation Service, U.S. Department of Agriculture, for a feasibility study of requirements for main ditch drainage canals in Williamsburg County, South Carolina. The maps have been prepared in cooperation with Williamsburg County Soil and Water Conservation District and under the financial sponsorship of Williamsburg County. For information regarding the complete feasibility study report, write the Soil Conservation Service, U.S. Department of Agriculture, Columbia, South Carolina. This map was compiled as an uncontrolled mosaic from aerial photographs flown in 1966. Maps were prepared and surveys executed in 1972.

(Joins sheet 12)



(Joins sheet 14)

0 1 2 3 4 5 Miles Scale 1:50,000 (As per contour)

0 1000 2000 3000 4000 5000 Feet

FEASIBILITY STUDY OF REQUIREMENTS FOR MAIN DRAINAGE CANALS IN WILLIAMSBURG COUNTY, SOUTH CAROLINA

14

(Joins sheet 12)

(Joins sheet 13)

